

Appendix E

Fluvial Geomorphology

Fluvial Geomorphology Study Fruitland-Winona Block 1 Servicing Strategy City of Hamilton, Ontario




Prepared for:
Urbantech Consulting
2030 Bristol Circle, Suite 105
Oakville, Ontario L6H 0H2

March 8, 2024
PN21043

GEO

M O R P H I X

Geomorphology
Earth Science
Observations



Report Prepared by: GEO Morphix Ltd.
36 Main Street North
PO Box 205
Campbellville, ON L0P 1B0

Report Title: Fluvial Geomorphology Study - Fruitland-Winona Block 1
Servicing Strategy

Project Number: PN21043

Status: Final

Version: 1.2

Prepared by: Lindsay Davis, M.Sc., P.Geo, CAN-CISEC,

Approved by: Paul Villard, Ph.D., P.Geo., CAN-CISEC, EP, CERP

Approval Date: March 8, 2024



Table of Contents

1	Introduction.....	1
2	Background Review	1
	2.1 Background Review.....	1
	2.2 Proposed Site Conditions	2
	2.3 Surficial Geology	2
3	Watercourse Characteristics.....	2
	3.1 Reach Delineation.....	2
	3.2 Field Observations	3
4	Erosion Threshold Analysis	5
	4.1 Methods	6
	4.2 Results.....	6
5	Post- and Pre-Development Erosion Exceedance Analysis	7
	5.1 Methods	8
	5.2 Results.....	9
6	Conceptual Channel Design	11
	6.1 Channel Planform	12
	6.2 Bankfull Channel	13
	6.3 Fish Passage	15
	6.4 Channel Corridor	15
	6.4.1 Corridor Sizing	15
	6.5 Habitat Restoration	16
	6.6 Wetland Replication	17
	6.7 Stormwater Management Outlet Design	17
7	Recommendations for Detailed Design	18
8	Post-Construction Monitoring Recommendations	18
9	Summary and Recommendations	18
10	References	20

List of Tables

Table 1. Reach characteristics summary.....	3
Table 2: Reach classifications summary	5




Table 3: Bankfull conditions and erosion threshold calculation parameters for the Watercourse 5 Reach WC5.....	7
Table 4: Results from the pre- to post-development erosion exceedance analysis for Reach WC5	10
Table 5: Bankfull parameters for the proposed channel.....	15
Table 6: Meander belt width estimate for design Reach WC5	16

Appendices

Appendix A Reach Mapping	A
Appendix B Photo Record	B
Appendix C Field Observations.....	C
Appendix D Detailed Assessment Summary.....	D
Appendix E Erosion Modelling Hydrographs	E



1 Introduction

GEO Morphix Ltd. was retained by Urbantech Consulting to complete a fluvial geomorphological assessment for the receiving watercourse associated with the proposed Stormwater Management (SWM) facilities within the Block 1 area. Two watercourse features traverse through the Block 1 property and are identified as **Watercourse 5 (WC5)** and **Watercourse 6 (WC6)**. To support future development plans, it is understood that **WC5** is proposed to be realigned and engineered, while **WC6** is proposed to remain in its natural state. Further, **WC5** is proposed to receive outflows from a SWM pond (Pond 1). An erosion assessment was assessment was complete for **WC5** to to determine if exacerbated rates of erosion could be anticipated within the watercourse as a consequence of development.

The following activities were completed as part of the fluvial geomorphological assessment:

- Review of pertinent background information, including conceptual development plans and previous reporting on the subject watercourse
- Desktop analysis to determine the potential zone of impact, which is the extent of the channel to be addressed
- Delineation and confirmation of stream reaches in the study area
- Rapid geomorphological field assessment to determine the stability of the receiving watercourse
- Completion of a detailed geomorphic assessment downstream of the proposed outlet locations, the primary objective of which is to support the critical flow or erosion threshold
- Determine erosion thresholds for the receiving watercourse
- Complete an erosion exceedance exercise comparing pre- and post-development hydrology provided by Urbantech Consulting (2021)

The following activities were completed in support of the proposed conceptual corridor realignments:


- Calculate bankfull channel dimensions for the proposed corridor alignments
- Channel planform, profile, and detail drawings
- Determine meander belt width for the low flow channel to ensure it can be accommodated within designed corridors
- Provide recommendations for wetland recreation within designed corridors

2 Background Review

2.1 Background Review

The Block 1 property is located in the western end of Stoney Creek, Ontario. The property is bound by Barton Road to the north, Fruitland Road to the west, Highway 8 to the south, and an agricultural property to the east. Existing land use throughout the property includes agricultural, rural residential, and commercial. Agricultural land-use is dominant throughout the interior of the subject property. However, these fields are no longer actively cultivated. Residential and commercial lands are present along the margins of the property.

Two watercourses, **Watercourse 5 (WC5)** and **Watercourse 6 (WC6)**, traverse the property, flowing in a south-to-north direction towards Lake Ontario. **WC5** enters the subject lands through



a culvert beneath Fruitland Road and runs parallel to the road on the western edge of the property. **WC5** passes through a short culvert crossing, associated with the existing commercial building in the northwest corner of the property, before exiting the subject property through a culvert under Barton Road. **WC6** flows into the property through a culvert passing under Highway 8. Flows travel north, parallel to Jones Road, and exits the property through a culvert passing beneath Barton Road.

A map of the study area is provided in **Appendix A**.

2.2 Proposed Site Conditions

The proposed development for Block 1 consists mainly of low- and medium-density residential units, with a community park, an elementary school, and some commercial lands. A 40 m wide channel block is proposed for **WC5**, with a portion of the channel set to be realigned within it. Three stormwater management (SWM) ponds are proposed within the property, with outlets discharging into either **WC5** or **WC6**. Of these, Pond 1 will discharge into **WC5** approximately 180 upstream of the Barton Street Culvert. Consequently, the channel section spanning from the Pond 1 outlet to the Barton Street culvert defines the zone of impact for the erosion assessment. The section spanning from Fruitland Road to the approximate outlet location is what is proposed to be realigned.

2.3 Surficial Geology

Channel morphodynamics are largely governed by the flow regime and the availability and type of sediments (i.e., surficial geology) within the stream corridor. These factors are explored as they not only offer insight into existing conditions, but also potential changes that could be expected in the future as they relate to a proposed activity. Understanding local surficial geology is important for determining appropriate erosion thresholds, as the stability of the channel banks and bed is dependent on the composition of soils, sediment, and underlying parent materials (MNR, 2002).

The Block 1 property resides within Iroquois Plain physiographic region (Chapman and Putnam, 1984). This region extends from the shores of Lake Ontario up to the base of the Niagara escarpment, and is characterized by heavy-textured, low-permeability soil derived from the shales of the underlying Queenston Formation. Broad gravel ridge formations exist from Stoney Creek to Hamilton, in which loams have developed with improved drainage. The surficial geology throughout the site is characterized entirely by the Paleozoic bedrock shales of the Queenston Formation (OGS, 2010).

3 Watercourse Characteristics

3.1 Reach Delineation

Reaches are homogeneous segments of channel used in geomorphological investigations. Reaches are divided as such because they are expected to have similar inputs and outputs in terms of sediments and discharge. They are also expected to react similarly throughout to flow events and other stressors. They are studied semi-independently as each is expected to function in a manner that is at least slightly different from adjoining reaches. This allows for a meaningful

characterization of a watercourse as the aggregate of reaches, or an understanding of a particular reach, for example, as it relates to a proposed activity.

Reaches are delineated based on changes in the following:

- Channel planform
- Channel gradient
- Physiography
- Land cover (land use or vegetation)
- Flow, due to tributary inputs
- Soil type and surficial geology
- Certain types of channel modifications by humans

This follows scientifically defensible methodology proposed by Montgomery and Buffington (1997), Richards et al. (1997), and the Toronto and Region Conservation Authority (2004).

Reaches are first delineated as a desktop exercise using available data and information such as aerial photography, topographic maps, geology information and physiography maps. The results are then verified in the field.

The existing reach delineation was adopted for this assessment, where a single reach (**WC5**) was delineated along **Watercourse 5** within the bounds of the property. This delineation was confirmed during the site visits described Section 3.2, and no additional reach breaks were identified. **Watercourse 6** was not assessed in this report, as it resides outside the zone of impact identified for scope of this assessment.


3.2 Field Observations

Rapid and detailed field assessments were completed as part of this study on August 19th, 2021 and January 31st, 2024. Photographs from the field assessments are provided in **Appendix B**, rapid field observations are provided in **Appendix C**, and the detailed assessment summary is provided in **Appendix D** for reference. A summary of the general observations characterizing the delineated reaches is presented in **Table 1**.

Table 1. Reach characteristics summary

Reach Name	Date Visited	Avg. Bankfull Width (m)	Avg. Bankfull Depth (m)	Riffle Substrate	Pool Substrate	Dominant Riparian Condition	Notes
WC5	2021-08-19	3.64	0.34	Clay	Clay	Established trees, shrubs	Straight channel with uniform trapezoidal cross-section, minimal geomorphic activity noted

Reach **WC5** is a straight, trapezoidal channel with little to no observable geomorphic activity or geomorphic unit development. The channel was likely straightened as part of the prior agricultural activities within the block. Pooled water was present in the reach during the assessment, but flows were imperceptible due to the low channel gradient. The bed and banks are comprised of a dense,



cohesive silty-clay. Banks are well-rooted from the established trees and shrubs that inhabit the riparian corridor.

Rapid Assessments

Rapid field assessments were completed for each of the identified reaches of the receiving watercourse. The rapid assessments were completed to identify the dominant local geomorphic processes, document stream health, and to identify any areas of concern regarding erosion or instability. This included the following observations for each reach:

- Characterization of stream form, process, and evolution using the Rapid Geomorphological Assessment (RGA) (MOE, 2003; VANR, 2007), which evaluates degradation, aggradation, widening, and planimetric form adjustment at the reach scale
- Assessment of the ecological function of the watercourse using the Rapid Stream Assessment Technique (RSAT) (Galli, 1996), which evaluates stream health based on a number of biological indicators
- Stream classification following a modified Downs (1995) and a modified Brierley and Fryirs (2005) River Styles Classification approach which evaluate the magnitude and potential for channel instability and indicate dominant sediment loads, respectively
- Instream estimates of bankfull channel geometry
- Bed and bank material composition and structure
- Georeferenced photographs to document the location of all observed erosion and infrastructure

Channel instability was objectively quantified through the application of the Ontario Ministry of the Environment's (MOE, 2003) Rapid Geomorphic Assessment (RGA). Observations were quantified using an index that identifies channel sensitivity based on evidence of aggradation, degradation, channel widening, and planimetric adjustment. The index produces values that indicate whether the channel is *stable/in regime* (score <0.20), *stressed/transitional* (score 0.21-0.40) or *adjusting* (score >0.41).

The Rapid Stream Assessment Technique (RSAT) was also employed to provide a broader view of the system and consider the ecological functioning of the watercourse (Galli, 1996). Observations were made of channel stability, channel scouring or sediment deposition, instream and riparian habitats, and water quality. The RSAT score ranks the channel as maintaining a *poor* (<13), *fair* (13-24), *good* (25-34) or *excellent* (35-42) degree of stream health.

The tributary was classified according to a modified Downs (1995) Channel Evolution Model, which describes successional stages of a channel as a result of a perturbation, namely hydromodification. Understanding the current stage of the system is beneficial as this allows one to predict how the channel will continue to evolve, or respond to an alteration to the system.

The River Styles Framework (Brierley and Fryirs, 2005) provides a geomorphic approach to examining river character, behaviour, condition, and recovery potential through the identification of the Geomorphic Process Zone. Geomorphic attributes are assessed, larger scale interactions between zones are analyzed, and historical data are studied in order to understand the historical evolution and future trajectories of those reaches. This ultimately provides a physical template for river management. A modified classification approach was applied to the study reaches.

A summary of the reach classifications and rapid assessment scores is provided in **Table 2**.

Table 2: Reach classifications summary

Reach Name	Date Visited	RGA Score	Dominant Process	RSAT Score	Downs Model Classification	River Styles Framework
WC5	2021-08-19	0.14	Widening	28	'm' – Lateral migration (initiating)	11 – Suspended load, straight

Reach **WC5** displayed minimal evidence of instability or erosion. This was reflected by the RGA score of 0.14, indicating a relatively stable channel. The dominant geomorphic process identified was widening, as it scored highest of the four indices in the RGA. **WC5** scored 28 on the RSAT, indicating an acceptable level of stream health. The reach was classified as a suspended load dominated, straight channel under the River Styles Framework (Brierley and Fryirs, 2005). Under the Downs (1995) model, the initiation of lateral migration was identified as the dominant channel forming mechanism.

Detailed Geomorphological Assessments

The detailed assessment, used to inform the erosion threshold analysis, was completed on reach **WC5** on August 19th, 2021. The downstream portion of reach **WC5** was selected for the detailed assessment, as it is situated downstream of the proposed outlet for Pond 1 and will receive discharges originating from the site. Activities completed for the detailed assessment included the following:


- Long-profile survey of the channel centre line
- Eight detailed cross-sectional surveys of the watercourse
- Detailed instream measurements at each cross-section location including bankfull channel geometry, riparian conditions, bank material, bank height/angle, and bank root density
- Bed material sampling at each cross-section following a modified Wolman's (1954) Pebble Count Technique or substrate sample
- Velocity and discharge measurements at select representative cross-sections

The resulting measured channel parameters are outlining **Table 3**, and a summary of the detailed assessment results is provided in **Appendix D**.

4 Erosion Threshold Analysis

Erosion thresholds are used to determine the magnitude of flow required to potentially entrain and transport bed and/or bank material. As such, they are used to inform erosion mitigation strategies in channels influenced by conceptual flow and stormwater management plans.

Erosion thresholds were determined from detailed field observations of reach **WC5**. The erosion threshold is the theoretical point, typically expressed as a critical discharge or shear stress, at which entrainment of sediment would occur based on bed and bank materials. Due to variability between bed and bank composition and structure, erosion thresholds are determined for both bed and bank materials. The lower of the bed and bank erosion thresholds is adopted, as it provides the more conservative and limiting estimate.



Threshold targets are determined using different methods that are dependent on channel and sediment characteristics. For example, thresholds for non-cohesive sediments are commonly estimated using a shear stress approach, similar to that of Miller et al. (1977), which is based on a modified Shield's curve. A velocity approach could also be applied, such as that described by Komar (1987). For cohesive materials, empirically derived values such as those compiled by Fischenich (2001), Chow (1959) or Julien (1998), could be applied.

4.1 Methods

An erosion threshold is quantified based on the bed and bank materials and local channel geometry, in the form of a critical discharge. Theoretically, above this discharge, entrainment and transport of sediment can occur. To determine this discharge, the velocity, U is calculated at various depths for a representative cross section until the average velocity in the cross section slightly exceeds the critical velocity of the bed material. The velocity is determined using a Manning's approach, where the Manning's n value is visually estimated through a method described by Acrement and Schneider (1989) or calculated using Limerino's (1970) approach. The velocity is mathematically represented as:

$$U = \frac{1}{n} d^{2/3} S^{1/2} \quad [\text{Eq. 1}]$$

where, d is depth of water, S is channel slope, and n is the Manning's roughness coefficient. The visual approach (Acrement and Schneider, 1989) was adopted for determining the Manning's roughness coefficient.

For the bank materials, following Chow (1959) in a simplified cross section, 75% of the bed shear stress acts on the channel banks. In a similar approach, the depth of flow is increased until the shear stress acting on the banks exceeds the resisting shear strength of the bank materials.

4.2 Results

Summarized results of the erosion threshold analysis are provided in **Table 3**. Reach **WC5** contains similar bed and bank materials, differentiated mainly by their level of compactness and water content. Bank material was identified as a non-colloidal silty loam with a corresponding critical velocity of 0.53 m/s. This critical velocity was adopted for the bed materials as well. As the bed material was more compact than the bank material, adopting the bank material critical velocity is a conservative approach with regards to erosion risk. Considering the material's level of cohesiveness, 0.53 m/s is a conservative estimate of the critical velocity itself.

Table 3: Bankfull conditions and erosion threshold calculation parameters for the Watercourse 5 Reach WC5

Channel parameter	Results by Reach
	WC5
Bankfull Conditions	
Average bankfull width (m)	3.64
Average bankfull depth (m)	0.56
Bankfull channel gradient (%)	0.76
D ₅₀ (mm)	<2
D ₈₄ (mm)	<2
Manning's n roughness coefficient	0.038
Bankfull discharge (m ³ /s)	1.31
Bankfull velocity (m/s)	1.06
Channel Bed Erosion Threshold	
Bed Material	Silty-clay loam, fairly compact
Apparent shear stress acting on bed (N/m ²)	7.30
Critical velocity at the bed (m/s)*	0.53
Critical discharge (m ³ /s)	0.116
Channel Banks Erosion Threshold	
Bank Material	Silty-clay loam, compact
Apparent shear stress acting on banks (N/m ²)	10.59
Critical velocity at the banks (m/s)*	0.53
Critical discharge (m ³ /s)	0.290
Limiting Critical discharge (m³/s)	0.116

* Criteria of Fischenich (2001) for non-colloidal silty loam

5 Post- and Pre-Development Erosion Exceedance Analysis

Using the results of the erosion threshold analysis and the provided hydrological modelling for post- and pre-development conditions, additional analyses regarding the impacts of SWM controls on potential erosion within the watercourses were completed with our own in-house model, based on four indices:

- 1) Cumulative time of exceedance
- 2) Number of exceedance events

- 3) Cumulative effective discharge
- 4) Cumulative effective work index (i.e. cumulative effective stream power)

These indices have been applied elsewhere in CH, TRCA, CVC, and other jurisdictions. They, as a product, provide an evaluation of the number of events, period of transport, and magnitude. We note that the most relevant indicator is the cumulative effective stream power.

Time of exceedance and number of exceedances can be simply calculated from the discharge record. For more relevant indicators, hydraulic information is required. Our model applies the discharge to a characteristic cross-section. Using a Manning's approach, the discharge at each time step in the continuous hydrological model is converted into a velocity, depth of flow, shear stress, and/or stream power. These parameters are calculated based on field measurements of slope, cross section and channel roughness. This provides analysis that is site appropriate and specific.

The post- and pre-development hydrological modelling reflects changes to the hydrological regime resulting from SWM measures being implemented within the catchment. Continuous flow data was provided by Urbantech Consulting (2021) in 5-minute increments for synthetic 25 mm, 2-year, 5-year, 10-year, 25-year, 50-year, and 100-year Chicago storm events. The hydrological modeling was analyzed to calculate the aforementioned erosion indices to identify changes in the erosive potential within **WC5** following development.

5.1 Methods

To calculate work terms, both velocity and shear stress were calculated at each time step. Through an iterative process, water depth and velocity were calculated for each discharge passing through a representative cross-section. The cross-section is divided into floodplain and bankfull sections. The cross-section is further broken into panels. Velocity, U , is calculated for each panel using the Manning's approach. This is a conservative approach as it allows dissipation of flood energy in the floodplain.

The total discharge, Q_T at each time step is based on the summation of the discharge of all panels, Q_i , such that:

$$Q_T = \sum Q_i \quad [\text{Eq. 2}]$$

Q_i is discharge through a panel (which is set at 10 percent of the cross-section). Q_i is defined as:

$$Q_i = U_i w_i d_i \quad [\text{Eq. 3}]$$

where, w_i and d_i are width and depth for each panel. The discharge for each panel was then summed to give a total discharge. This is more accurate than using average cross-sectional dimensions of a simple trapezoidal channel, as the bed is usually irregular, and a panel approach more accurately represents the true cross-sectional area.

For each event, the discharge is converted into a maximum depth and average velocity. The maximum depth is used to calculate a maximum bed shear stress, $\tau_{o_{\max}}$ based on:

$$\tau_{o_{\max}} = d_{\max} \rho g S_{\text{bed}} \quad [\text{Eq. 4}]$$

where, d_{\max} is the maximum water depth, ρ is water density, g is acceleration due to gravity, and S_{bed} is the channel bed slope.

Cumulative total work, ω_{tot} is defined as:

$$\omega_{\text{tot}} = \sum \tau_{0\max} \cdot U_{\text{avg}} \cdot \Delta t \quad [\text{Eq. 5}]$$

where, U_{avg} is average velocity ($Q_{\text{tot}}/A_{\text{tot}}$, where A_{tot} is wetted area), while cumulative effective work index (ω_{eff}) is defined by:

$$\omega_{\text{eff}} = \sum \tau - \tau_{\text{cr}} \cdot U \cdot \Delta t, \omega < 0 = 0 \quad [\text{Eq. 6}]$$

where, τ_{cr} is the critical shear stress.

Time of exceedance t_{ex} defined as:

$$t_{\text{ex}} = \sum \Delta t \text{ for } (Q_T > Q_{\text{threshold}}) \quad [\text{Eq. 7}]$$


where, $Q_{\text{threshold}}$ is the discharge at the erosion threshold.

5.2 Results

The full series of post- to pre-development hydrographs are included in **Appendix E**, and include the erosion threshold based on discharge, for reference. **Table 4** provides the results of the assessment based on the hydrographs provided by Urbantech Consulting (2021).

Table 4: Results from the post- and pre-development erosion exceedance analysis for Reach WC5

Simulation		CED (m ³ /s)	ω_{eff} (N/m ²)	t_{ex} (hrs)
25 mm	(PRE)	0.95	16.49	3.25
	(POST)	0.98	15.04	3.92
	Change (%)	3.10%	-8.79%	20.51%
2-year	(PRE)	6.45	135.52	15.00
	(POST)	7.83	168.78	17.08
	Change (%)	21.29%	24.55%	13.89%
5-year	(PRE)	12.18	280.67	18.42
	(POST)	14.46	340.20	20.42
	Change (%)	18.73%	21.21%	10.86%
10-year	(PRE)	16.45	376.81	20.25
	(POST)	19.29	454.25	22.17
	Change (%)	17.28%	20.55%	9.47%
25-year	(PRE)	22.44	497.47	22.33
	(POST)	25.98	584.02	24.17
	Change (%)	15.77%	17.40%	8.21%
50-year	(PRE)	26.77	574.64	23.58
	(POST)	30.75	659.04	25.25
	Change (%)	14.89%	14.69%	7.07%
100-year	(PRE)	31.27	648.04	24.67
	(POST)	35.71	724.56	26.33
	Change (%)	14.19%	11.81%	6.76%



It is noted that the cumulative effective discharge (CED) and cumulative effective work index (ω_{eff}) are considered the most relevant erosion indices, as they reflect both the severity and duration of an exceedance event. Further, storms of moderate magnitudes and of relatively frequent recurrence typically exert the most influence on a given channel's geomorphic regime. Results from the 25 mm event and, to a lesser extent, the 2-year event are therefore the most relevant storm simulations in the context of evaluating erosion potential following hydrological regime changes.

For the 25 mm storm, the CED saw a minor increase of 3.10% from pre- to post-development hydrological conditions. The ω_{eff} decreased by 8.79% and the cumulative exceedance duration (t_{ex}) increased by 20.51%. For the 2-year event, the CED, ω_{eff} , and t_{ex} increased by 21.29%, 24.55%, and 13.89%, respectively. Increases in all indices were predicted for the larger storm events. The magnitude of these predicted increases consistently tapers off as storm magnitudes increase, reaching 14.19%, 11.81%, and 3.76% for the 100-year event CED, ω_{eff} , and t_{ex} , respectively.

The notable decrease in erosion potential predicted for the 25 mm event is expected to offset the moderate increases predicted for the larger, less frequent storms. Thus, the modelling results indicate that exacerbated rates of erosion resulting from development will not occur within reach **WC5**.

6 Conceptual Channel Design

As part of the Stoney Creek Urban Boundary Expansion (SCUBE) Phase 3, **WC5** was identified to be restored and realigned, which provides opportunity to replace the existing morphologically-limited channel with a naturalized riffle and pool typology, with cross sectional dimensions closer to that of a naturalized watercourse conveying similar flows. One goal of the natural channel design is to replace the existing degraded channel that has been impacted by past agricultural and development activities. A naturalized watercourse will offer significant improvements to channel form and function, per unit length.

The realignment and naturalization provide opportunities for improved riparian conditions and a well-developed bankfull channel with morphological variability. Improvement in morphology and function will provide additional benefits to sediment balance, floodplain storage, vegetation communities and terrestrial habitat features, aquatic habitat, edge impacts, water balance, fish passage and water quality.

The primary objectives of the design are to:

- Restore the physical form of the channel including planform and in-channel characteristics
- Ensure channel stability and function during low flow periods
- Create low-flow channel that accommodates the bankfull discharge to improve the function of the channel corridor and increase interactions with the floodplain
- Create a floodplain that includes interconnected wet meadow and linear wetland features of variable depth, shape, and hydroperiod
- Provide a mix of coarse and fine sediment sources throughout the low-flow channel and floodplain

- Enhance aquatic habitat for warmwater fish through the provision of a morphologically diverse channel with spatially varied flows
- Improve riparian habitat by installing woody plantings and dynamic floodplain features
- Mitigate potential hazards to the development as well as lands surrounding the development

Technical details are provided in subsequent sections to outline the approach used for channel sizing and habitat restoration.

6.1 Channel Planform

The initial channel planform layout will be created using the modelled radius of curvature value (R_c) as a guide. The radius of curvature (R_c) of meanders can be used to evaluate channel stability. For example, stable meanders typically exhibit larger R_c values as opposed to lower values that indicate increased channel bank erosion and avulsion. Bankfull width is often an appropriate indicator for this instability. Hickin and Nanson (1983) note that channel avulsions are common when meander R_c is approximately 1-2 times the channel bankfull width. For larger R_c (e.g., >5), the upstream limb of the meander will migrate more rapidly than the downstream limb (Hooke, 1975). Williams (1986) was used to derive values for the channel radius of curvature, using the following equation (Eq. 8):

$$R_c = 2.43 \times w \quad [\text{Eq. 8}]$$

where R_c is the radius of curvature and w is the average bankfull width.

Empirical models derived by Hey and Thorne (1986) were followed to determine riffle spacing. Hey and Thorne's (1986) modelled values are often applied in larger watercourses. As such, multiple methods (Eq. 9-11) were considered in order to provide a range of riffle spacing values. These are:

$$Z = 6.31 \times w \quad [\text{Eq. 9}]$$

$$Z = 9.1186 \times w^{0.8846} \quad [\text{Eq. 10}]$$


$$Z = 7.36 \times w^{0.896} \times S^{-0.03} \quad [\text{Eq. 11}]$$

where Z represents riffle spacing.

Stream power and unit stream power were calculated as a function of bankfull discharge and channel gradient (Eq. 12-13). Stream power values are important to determine the need for mitigating channel bank and bed erosion. Stream power is given by:

$$\Omega = \rho \times g \times d \times S \quad [\text{Eq. 12}]$$

where ρ is the density of water (kg/m^3), g is the acceleration due to gravity (m/s^2), and Q and S are discharge (m^3/s) and channel gradient, respectively.



Stream power per unit width (Eq. 13), is given by:

$$\omega = \frac{\Omega}{w} \quad [\text{Eq. 13}]$$

where as before, Ω and w are stream power and bankfull width, respectively.

The final channel planform will be established through an iterative process. First, a cross section with defined bankfull geometry was developed to calculate parameters for the planform (i.e., radius of curvature). The cross section will then be further refined, and riffle and pool lengths will be determined based on channel gradient.

6.2 Bankfull Channel

The recommended restoration design focuses on a riffle and pool sequences. The riffle and pool sequences will provide significant improvements to not only the channel, as it essentially mimics a natural system, but also to aquatic habitat. In summary, the riffle-pool system offers numerous benefits, namely:

- Channel bed relief for flow variability
- Water aeration in riffle sections
- Relatively quiescent flows in pool sections to provide refuge for fish during high flows
- Increased depths in pools to provide relatively cool water
- In-channel energy dissipation

Channel design dimensions are determined by bankfull discharge, as this represents what is generally referred to as the “*channel-forming discharge*” or the “*dominant discharge*”. Several methods can be applied to select an appropriate bankfull discharge. Back calculation of discharge from a reference reach along with support from hydrological modelling is usually the most appropriate. Due to changes in hydrology likely to occur because of the proposed development on site, a discharge based on hydrological modelling was determined for **WC5** and then subsequently used to define channel bankfull geometry. The discharge used to size the bankfull channel was assumed to be equivalent to the modelled 2-year flow. As such, the bankfull discharge was defined as 1.40 m³/s, based on hydrological modelling provided by Urbantech Consulting Engineers (2021). Bankfull capacity for channels generally have a range from the 1- to 2-year return events. The bankfull channel geometries are provided for guidance for the design concept and can be further refined based on subsequent studies.

A simple Manning’s approach was used to iteratively back-calculate bankfull dimensions for the proposed channel. Since pools are designed to contain ineffective space, this model over-predicts the amount of discharge that they convey. As such, the modelled values for the riffles give a better prediction of the channel’s capacity. Average channel geometries, as well as anticipated bankfull conditions for the proposed channel, are provided in **Table 5**.

Table 5: Average bankfull parameters for the proposed channel

Channel parameter	Reach 1	
	Riffle	Pool
Average bankfull width (m)	2.50	3.65
Average bankfull depth (m)	0.32	0.39
Maximum bankfull depth (m)	0.45	0.70
Bankfull width-to-depth ratio	7.89	9.25
Riffle gradient (%)	2.40	0.68
Bankfull gradient (%)	0.68	0.68
Average radius of curvature (m)	22	
Riffle-pool spacing (m)	8	
Manning's roughness coefficient, <i>n</i>	0.035	0.04
Mean bankfull velocity (m/s)	1.77	0.97
Bankfull discharge (m ³ /s) *	1.40	1.40
Discharge to accommodate (m ³ /s)	1.40	1.40
Tractive force at bankfull (N/m ²)	106	47
Stream power (W/m)	330	93
Unit stream power (W/m ²)	132	43
Froude Number (unitless)	1.0	0.50
Maximum grain size entrained (m) **	0.11	0.05
Mean grain size entrained (m)**	0.08	0.03

* Based on Manning's equation; using riffle gradient as pools contain ineffective space, the velocity and discharge conveyed in them are not representative

** Based on a modified Shields equation (Miller et al. 1977), assuming Shields parameter equals 0.06 for gravel

The sizing of proposed substrate materials was guided by a review of hydraulic conditions (i.e., tractive force, flow competency) in the typical cross sections. The channel bed substrate is derived by balancing the average shear stress acting on the bed with the critical shear stress for the material. When the critical shear stress slightly exceeds the average shear stress acting on the bed, sediment transport is initiated.

To provide for a stable bed and level of sorting, 40% 50 mm – 100 mm diameter riverstone, 30% granular 'b' and 30% native material is proposed for the riffles. Granular 'b' consists of a mix of stone where approximately 20% - 50% of the stone is greater than 0.005 m in diameter, but nothing larger than 0.15 m in diameter. These materials will always have a core of sediment that is not entrained under bankfull flow conditions. This material maintains the character of the native material, while providing slightly higher stability and opportunity for sediment sorting. A mix of granular 'B' and native material is proposed for the pools given they experience lower velocities. Hydraulic sizing should be confirmed during detailed design once the channel geometries and flows have been finalized.

6.3 Fish Passage

The near-bed velocity within the channel was modelled to determine whether fish passage is possible under the range of conditions expected for the low-flow channel. The velocity increases logarithmically with height above the bed surface in turbulent flows, through a relationship known as the von Karmen equation, or the Law of the Wall. Based on a knowledge of the bed materials, a theoretical height above the bed where velocity equals zero can be determined. The von Karmen equation is typically used to estimate the shear stress at the bed surface. However, a near-bed velocity can be back calculated using the average shear stress predicted for the low flow channel. The modelled velocities at a 0.01 m depth from the channel bed for the realigned channel was approximately 0.37 m/s in the riffles at the 2-yr return flow.

These values are within the range of velocities tolerated by various species found within the watershed (i.e., brook stickleback, creek chub, etc.; Katopodis and Gervais, 2016). Additionally, channels with gradients less than 5.0% are possible for fish passage, and the realigned channel has gradients that are less than 5.0% (Newbury, 2013). As a result, the gradients and velocities within the realigned channel are not detrimental to fish passage for local species.

6.4 Channel Corridor

6.4.1 Corridor Sizing

Meander belt width delineation was completed in support of defining erosion requirements for the realigned watercourse within the proposed development. With regards to delineating the hazard associated with channel migration, the Ontario Ministry of Natural Resources treats confined and unconfined systems differently. Unconfined systems are those with poorly defined valleys or slopes well outside where the channel could realistically migrate. In unconfined systems, the hazard is assumed to be from channel migration. Unconfined systems require a meander belt width. Given the size of the existing channel compared to the floodplain, this channel can be considered unconfined.

As part of the design, a meander belt width was calculated based on design bankfull dimensions of the channel to ensure that the planform has a meander belt width that falls within the proposed corridor requirements. Given the scale of the watercourse and limited migration potential for the system, the hazard limits calculated can be considered conservative. The meander belt widths provided are based on a modelled relation from Williams (1986) which were modified to include channel width and a factor of safety, and applied using the bankfull channel dimensions such that:

$$B_w = (4.3W_b^{1.12} + W_b) \times 1.2 \quad [\text{Eq. 16}]$$

where B_w is meander belt width (m), and W_b is bankfull channel width (m). An additional 20% buffer, or factor of safety, was applied to the computed belt width values. This addresses issues of under prediction and provides a factor of safety.

The bankfull channel dimensions of the proposed channel have an average width of 3.10 m. The resulting meander belt width estimates are provided in **Table 6**.

Table 6: Meander belt width estimate for design WC5

Omagh Tributary	Meander Belt Width (m)*	Corridor Bottom Width (m)
Design Reach 1	23	23

* Includes 20% factor of safety

The predicted meander belt width for realigned **WC5** is 23 m based on the proposed flows and corridor gradient. All meander belt width calculations are based on channels where instream energy is greater than potential resistance of the bank materials. As such, they over predict the potential extent of meandering of vegetation-controlled channels and the erosion hazard. The proposed valley bottom width for **WC5** of 23 m adequately addresses the erosion hazard.

6.5 Habitat Restoration

The design incorporates several habitat elements within the channel corridor to improve riparian habitat and promote wildlife biodiversity. To maximize potential for wildlife passage, forage and residency, the habitat design incorporates varying topographies and woody debris. The habitat elements proposed include tortuous meanders, brush mattresses, basking logs, pallet type wood piles, raptor poles, rock piles, and terrestrial mounds.


Potential overwintering deep sections are proposed to provide critical habitat for resident fish. The overwintering deep sections are provided within the tortuous meander pattern, which will increase scour and depth. Overwintering deep sections will be 0.35 m deeper than the typical proposed pools. This habitat feature will provide fish with potential refuge from freezing conditions in the winter, but also provide ideal habitat during low flow periods, and increase habitat heterogeneity within the channel. Due to the size of the proposed channel the pools could freeze completely during the winter.

Brush mattress is proposed along the outside meander bend of the tortuous meanders and at the connection with the conveyance swale at the upstream extent. This treatment consists of live brush cuttings installed parallel to the banks and tied in with coir twine and stakes. The brush mattress will provide bank stability and improve aquatic habitat through shading.

Basking logs consist of a mixture of hardwood and softwood species, place in shallow areas of wetlands and anchored with a mix of stone or limestone blocks. These logs are angled in a way to promote turtle basking.

Pallet type wood piles consist of logs, snags and other wood debris, placed in a way that forms a stable interconnected mound, in the shape of a pallet. Additionally, the wood piles are planted with native fruit bearing vines, which provide forage opportunities for wildlife. Wood piles are placed at various locations along the length of the floodplain.

Raptor poles are constructed from large conifer tree trunks, embedded into the ground and serve to provide perches for larger raptors.



Rock piles consist of a mix of stone of varying sizes, piled up to create small mounds. These features provide hibernation habitat for various terrestrial species. The base of the piles is partially buried to prevent rock falls. Rock piles are installed at various locations along the length of the floodplain.

Terrestrial mounds consist of native material, piled up to create small mounds with a small dimple on the top. The bottom of the mound is seeded with the specified seed mix, while the top has limited soil and seed on it to provide foraging opportunities.

The full channel corridor will be restored using native plant species. This includes appropriate species for the various seed mixes as well as woody vegetation. The plantings are intended to enhance the terrestrial habitat through the provision of species and habitat diversity, increase floodplain soil stability and floodplain roughness, and increase sedimentation. The landscaping plan will be prepared at detailed design.

6.6 Wetland Replication

Offline wetland features will be constructed in addition to the channel. These features enhance terrestrial habitat by increasing diversity and providing a more natural floodplain form. They also provide functional benefits such as short-term water retention and sediment banking. They will be irregularly shaped to maximize the perimeter for a given area, which increases the potential for edge effects. Submerged and dry mounds are proposed within the offline wetlands to provide a topographically complex bottom to increase habitat heterogeneity. The short-term water retention function of these wetland types helps to polish water and moderate the discharge of water into the channel. These features will address the proposed wetland replication due to the removal of the existing wetland feature.

Wetland replication is proposed as part of the development to compensate for the removal of existing wetlands. Within the **WC5** corridor 0.46 ha of wetland is provided, which accounts for approximately 30% of the floodplain. The proposed wetlands have an average depth of 0.60 m. The wetlands were designed with mounds of variable heights to allow for a range of wetland vegetation to establish. We have provided variability to assure that from year-to-year a range of water depths and hydroperiods are provided. The proposed restoration planting plan will be completed at detailed design.

6.7 Stormwater Management Outlet Design

Stormwater management Pond 1 is proposed to outlet to the **WC5** corridor. We recommend a stone core wetland be installed at the proposed outfall. The stone core refers to hydraulically sized rounded stone, which is the subsurface material used to ensure wetland stability. The stone should be hydraulically sized to withstand the pipe capacity or maximum outflow velocity from the SWMP outlet and should include a 20% factor of safety. The wetland should be constructed as an over-excavated depression which is lined with a mix of soil and granular materials, to provide both depressional and subsurface storage (within the interstitial space of the sediment and soil). A layer of topsoil will be installed on top of the stone core to improve vegetation establishment within the feature. Filtration is provided as a result of flow through the soil medium between the pocket wetland a proposed channel.



7 Recommendations for Detailed Design

To support detailed design and ensure proper implementation of the channel corridors, the following activities are recommended at the detailed design stages:

- Confirm valley and channel gradients
- Develop planform and profile for the proposed corridors
- Develop a native planting plan for the proposed corridors
- Confirm hydraulic stone sizing to ensure the channel is stable
- Determine potential locations for additional terrestrial habitat features within each corridor
- Develop recommendations for implementation during construction, including an erosion and sediment control plan
- Develop and finalize a post-construction monitoring plan for the realigned channels


8 Post-Construction Monitoring Recommendations

A post-construction monitoring program is recommended to assess the performance of the implemented channel design. Monitoring observations can also be used to determine the need for remedial works, if required. Monitoring is recommended for three full calendar years after construction and includes annual visual inspections and surveys. The following monitoring and reporting activities are suggested for the realigned channel:

- General observations of the channel works should be documented after construction and after the first large flooding event to identify any potential areas of erosion concern
- Collection of a photographic record of site conditions
- Total station survey of the longitudinal profile and monumented cross sections following construction. This would serve as the as-built reference condition for use in comparing surveys completed in subsequent years
- Re-survey of the longitudinal profile and cross sections in subsequent years after construction
- Installation of erosion pins at monumented cross sections after construction and monitoring of the erosion pins during subsequent years
- Bed material characterization based on Wolman (1954) pebble counts
- General vegetation surveys completed annually after construction, for the duration of the monitoring period to determine survivorship of the plant materials (any dead, diseased or damaged plant materials will be replaced within the warranty period)
- Annual reporting to summarize construction activities (i.e., design implementation), and subsequent year-end reports for the duration of the monitoring period

9 Summary and Recommendations

The purpose of this study was to investigate the potential for excess erosion to occur in the receiving watercourse associated with the SWM outflows from the proposed development within the Block 1 property, Hamilton. Reconnaissance-level field assessments of the receiving watercourse (**WC5**) were completed to characterize the system and identify erosion-sensitive locations within the zone of impact. A detailed geomorphic assessment was completed within the



zone of impact along reach **WC5**, from which an erosion threshold was computed and provided as a critical discharge. For reach **WC5**, a critical discharge of $0.116 \text{ m}^3/\text{s}$ was determined based on a critical velocity of 0.53 m/s acting on the silty-clay bed materials (Fischenich, 2001).

Erosion exceedance modelling results indicate that the proposed stormwater management plan adequately addresses the concerns regarding potential excess erosion within WC5 following development. A reduction in erosion potential was predicted for the 25 mm, and a moderate increase in erosion potential was predicted for the larger, less-frequent storms. Considering the reduction in erosion potential predicted for the highly relevant 25 mm event, we do not foresee the requirement for any changes to the proposed stormwater management plan, or for the requirement of any additionally systemic erosion protection measures, as the assimilative capacity of the receiving watercourse is sufficient for the proposed changes to the hydrological regime.

We trust this report meets your requirements. Should you have any questions please contact the undersigned.

Respectfully submitted,



Paul Villard Ph.D., P.Geo., CAN-CISEC, EP, CERP
Director, Principal Geomorphologist




Lindsay Davis, M.Sc., P.Geo., CAN-CISEC
Geomorphologist



10 References

- Brierley, G. J. and Fryirs, K. A. 2005. *Geomorphology and River Management: Applications of the River Styles Framework*. Blackwell Publishing, Oxford, UK, 398pp.
- Downs, P.W. 1995. Estimating the probability of river channel adjustment. *Earth Surface Processes and Landforms*, 20: 687-705.
- Chapman, L.J. and Putnam, D.F. 1984. *The Physiography of Southern Ontario*. Ontario Geological Survey, Special Volume 2, Map 226.
- Chow, V.T. 1959. *Open channel hydraulics*. McGraw Hill, New York.
- Fischenich, C. 2001. *Stability Thresholds for Stream Restoration Materials*. EMRRP Technical Notes Collection (ERDC TN-EMRRP-SR-29), U.S. Army Engineer Research and Development Center, Vicksburg, MS.
- Galli, J. 1996. *Rapid Stream Assessment Technique, Field Methods*. Metropolitan Washington Council of Governments.
- Hey, R. D. and Thorne, C. R. 1986. Stable channels with mobile gravel beds. *Journal of Hydraulic Engineering*, American Society of Civil Engineers 112: 671-689.
- Hickin, E.J. and Nanson, G.C. 1984. Lateral migration rates of river bends. *Journal of Hydraulic Engineering*, 110: 1557-1567.
- Hooke, J.M. 1975. Distribution of sediment transport and shear stress in a meander bend. *Journal of Geology*, 83: 543-566.
- Julien, P. Y. 1998. *Erosion and Sedimentation* (1st ed.). Cambridge University Press.
- Katopodis, C. and Gervais, R. 2016. *Fish swimming performance database and analyses*. DFO Can. Sci. Advis. Sec. Res. Doc. 2016/002. vi + 550 p
- Komar, P.D. 1987. Selective gravel entrainment and the empirical evaluation of flow competence. *Sedimentology*, 34: 1165-1176
- Limerinos, J.T. 1970: Determination of the Manning coefficient from measured bed roughness in natural channels. United States Geological Survey Water-Supply Paper 1898B.
- Miller, M.C., McCave, I.N. and Komar, P.D. 1977. Threshold of sediment erosion under unidirectional currents. *Sedimentology*, 24: 507-527.
- Ministry of Environment (MOE). 2003. Ontario Ministry of Environment. *Stormwater Management Guidelines*.
- Montgomery, D.R. and J.M. Buffington. 1997. Channel-reach morphology in mountain drainage basins. *Geological Society of America Bulletin*, 109 (5): 596-611.
- Neill, C.R. 1967. Mean-velocity criterion for scour of coarse uniform bed material. *Proceedings of the 12th Congress, International Association of Hydraulic Research*, 3, 46-54.
- Newbury, R.W. 2013. Designing fish-passable riffles as gradient controls in Canadian streams. *Canadian Water Resources Journal*, 38: 232-250.



Ontario Geological Survey (OGS). 2010. Surficial geology of Southern Ontario. Ontario Geological Survey. Miscellaneous Release – Data 128-REV.

Richards, C., Haro, R.J., Johnson, L.B. and Host, G.E. 1997. Catchment and reach-scale properties as indicators of macroinvertebrate species traits. *Freshwater Biology*, 37: 219-230.

Toronto and Region Conservation Authority. 2004. Belt Width Delineation Procedures.


Vermont Agency of Natural Resources (VANR). 2007. Step 7: Rapid Geomorphic Assessment (RGA). Phase 2 Stream Geomorphic Assessment.

Williams, G.P. 1986. River meanders and channel size. *Journal of Hydrology*, 88 (1-2): 147-164.




Appendix A

Reach Mapping



- Legend**
- Watercourse
 - Contour (1 m)
 - Detailed Assessment
 - Subject Property

Reach Delineation
Fruitland-Winona Block 1 Servicing Strategy
 Hamilton, Ontario



Imagery: Google Earth Pro: 2018
 Subject Property: Parish Aquatic Services, 2019.
 Watercourse and 1 m Contour: City of Hamilton, 2020.
 Detailed Assessment: GEO Morphix Ltd., 2021.
 Printed: March 2022. PN21043. Drawn by: J.T., M.O.



Appendix B

Photo Record

Photo 1
Reach **WC5**



Flows enter reach **WC5** through a concrete box culvert passing under Fruitland Road. No erosion concerns were noted. Yellow arrow denotes flow direction.

Photo 2
Reach **WC5**



No bed scour was noted downstream of the Fruitland Road culvert.

Photo 3
Reach **WC5**



Reach **WC5** has a predominantly trapezoidal channel shape throughout the study area. Minimal flow velocities were observed during the assessment.

Photo 4
Reach **WC5**



Bank materials across the entire reach are characterized by silty clay. Occasional tree roots were observed, but the bottom third of the bank is typically exposed.

Photo 5
Reach **WC5**



Bed materials are consistent with the bank materials but are much less compact. Algae is abundant throughout the reach.

Photo 6
Reach **WC5**



Exposed material is common at toe of bank. Riparian vegetation provides some level of stabilization, but roots are typically small and immature.

Photo 7
Reach **WC5**



Several sections of shallow flow, abundant debris, and loose bed material are present. Debris is largely associated with past agricultural infrastructure.

Photo 8
Reach **WC5**



A small footbridge is present in **WC5**. A thick debris jam exists immediately upstream and retains a level of flow.

Photo 9
Reach **WC5**



Downstream of the footbridge, debris marks are visible on several flow-impeding trees, indicating the approximate bankfull flow stage.

Photo 10
Reach **WC5**



Bank armouring and a footbridge were observed further downstream. This infrastructure is significantly degraded and has evidently not been maintained for many years.

Photo 11
Reach **WC5**



Flows near the downstream extent of the reach are slightly deeper. The channel width expands in this section. The leaning trees indicate a level of channel widening.

Photo 12
Reach **WC5**



Evidence of erosion largely subsides near the downstream extent, as the channel exhibits more depositional tendencies, indicated by siltation on the bed.



Appendix C

Field Observations

Rapid Geomorphic Assessment

Project Code: 21043

Date:	2021-08-19	Stream/Reach:	Watercourse 5
Weather:		Location:	Hamilton
Field Staff:	JT DM	Watershed/Subwatershed:	

Process	Geomorphic Indicator		Present?		Factor Value
	No.	Description	Yes	No	
Evidence of Aggradation (AI)	1	Lobate bar		X	1/6
	2	Coarse materials in riffles embedded			
	3	Siltation in pools	X		
	4	Medial bars		X	
	5	Accretion on point bars		X	
	6	Poor longitudinal sorting of bed materials		X	
	7	Deposition in the overbank zone		X	
Sum of indices =			1	5	0.167

Evidence of Degradation (DI)	1	Exposed bridge footing(s)			0/6
	2	Exposed sanitary / storm sewer / pipeline / etc.			
	3	Elevated storm sewer outfall(s)			
	4	Undermined gabion baskets / concrete aprons / etc.			
	5	Scour pools downstream of culverts / storm sewer outlets		X	
	6	Cut face on bar forms		X	
	7	Head cutting due to knick point migration		X	
	8	Terrace cut through older bar material		X	
	9	Suspended armour layer visible in bank		X	
	10	Channel worn into undisturbed overburden / bedrock		X	
Sum of indices =			0	6	0

Evidence of Widening (WI)	1	Fallen / leaning trees / fence posts / etc.	X		3/8
	2	Occurrence of large organic debris		X	
	3	Exposed tree roots	X		
	4	Basal scour on inside meander bends		X	
	5	Basal scour on both sides of channel through riffle	X		
	6	Outflanked gabion baskets / concrete walls / etc.		X	
	7	Length of basal scour >50% through subject reach		X	
	8	Exposed length of previously buried pipe / cable / etc.			
	9	Fracture lines along top of bank		X	
	10	Exposed building foundation			
Sum of indices =			3	5	0.375

Evidence of Planimetric Form Adjustment (PI)	1	Formation of chute(s)		X	0
	2	Single thread channel to multiple channel		X	
	3	Evolution of pool-riffle form to low bed relief form		X	
	4	Cut-off channel(s)		X	
	5	Formation of island(s)		X	
	6	Thalweg alignment out of phase with meander form		X	
	7	Bar forms poorly formed / reworked / removed		X	
Sum of indices =					0

Additional notes: - Min observable geomorphic activity		Stability Index (SI) = (AI+DI+WI+PI)/4 = 0.14			
		Condition	In Regime	In Transition/Stress	In Adjustment
		SI score =	☐ 0.00 - 0.20	☐ 0.21 - 0.40	☐ 0.41

Completed by: _____ Checked by: _____

Rapid Stream Assessment Technique

Project Code: 21043

Date:	2021-08-19	Stream/Reach:	Watercourse 5
Weather:		Location:	Hamilton
Field Staff:	JT DM	Watershed/Subwatershed:	

Evaluation Category	Poor	Fair	Good	Excellent
Channel Stability	<ul style="list-style-type: none"> < 50% of bank network stable Recent bank sloughing, slumping or failure frequently observed 	<ul style="list-style-type: none"> 50-70% of bank network stable Recent signs of bank sloughing, slumping or failure fairly common 	<ul style="list-style-type: none"> 71-80% of bank network stable Infrequent signs of bank sloughing, slumping or failure 	<ul style="list-style-type: none"> > 80% of bank network stable No evidence of bank sloughing, slumping or failure
	<ul style="list-style-type: none"> Stream bend areas highly unstable Outer bank height 1.2 m above stream bank (2.1 m above stream bank for large mainstem areas) Bank overhang > 0.8-1.0 m 	<ul style="list-style-type: none"> Stream bend areas unstable Outer bank height 0.9-1.2 m above stream bank (1.5-2.1 m above stream bank for large mainstem areas) Bank overhang 0.8-0.9m 	<ul style="list-style-type: none"> Stream bend areas stable Outer bank height 0.6-0.9 m above stream bank (1.2-1.5 m above stream bank for large mainstem areas) Bank overhang 0.6-0.8 m 	<ul style="list-style-type: none"> Stream bend areas very stable Height < 0.6 m above stream (< 1.2 m above stream bank for large mainstem areas) Bank overhang < 0.6 m
	<ul style="list-style-type: none"> Young exposed tree roots abundant > 6 recent large tree falls per stream mile 	<ul style="list-style-type: none"> Young exposed tree roots common 4-5 recent large tree falls per stream mile 	<ul style="list-style-type: none"> Exposed tree roots predominantly old and large, smaller young roots scarce 2-3 recent large tree falls per stream mile 	<ul style="list-style-type: none"> Exposed tree roots old, large and woody Generally 0-1 recent large tree falls per stream mile
	<ul style="list-style-type: none"> Bottom 1/3 of bank is highly erodible material Plant/soil matrix severely compromised 	<ul style="list-style-type: none"> Bottom 1/3 of bank is generally highly erodible material Plant/soil matrix compromised 	<ul style="list-style-type: none"> Bottom 1/3 of bank is generally highly resistant plant/soil matrix or material 	<ul style="list-style-type: none"> Bottom 1/3 of bank is generally highly resistant plant/soil matrix or material
	<ul style="list-style-type: none"> Channel cross-section is generally trapezoidally-shaped 	<ul style="list-style-type: none"> Channel cross-section is generally trapezoidally-shaped 	<ul style="list-style-type: none"> Channel cross-section is generally V- or U-shaped 	<ul style="list-style-type: none"> Channel cross-section is generally V- or U-shaped
Point range	<input type="checkbox"/> 0 <input type="checkbox"/> 1 <input type="checkbox"/> 2	<input type="checkbox"/> 3 <input type="checkbox"/> 4 <input type="checkbox"/> 5	<input type="checkbox"/> 6 <input checked="" type="checkbox"/> 7 <input type="checkbox"/> 8	<input type="checkbox"/> 9 <input type="checkbox"/> 10 <input type="checkbox"/> 11

Channel Scouring/ Sediment Deposition	<ul style="list-style-type: none"> > 75% embedded (> 85% embedded for large mainstem areas) 	<ul style="list-style-type: none"> 50-75% embedded (60-85% embedded for large mainstem areas) 	<ul style="list-style-type: none"> 25-49% embedded (35-59% embedded for large mainstem areas) 	<ul style="list-style-type: none"> Riffle embeddedness < 25% sand-silt (< 35% embedded for large mainstem areas)
	<ul style="list-style-type: none"> Few, if any, deep pools Pool substrate composition >81% sand-silt 	<ul style="list-style-type: none"> Low to moderate number of deep pools Pool substrate composition 60-80% sand-silt 	<ul style="list-style-type: none"> Moderate number of deep pools Pool substrate composition 30-59% sand-silt 	<ul style="list-style-type: none"> High number of deep pools (> 61 cm deep) (> 122 cm deep for large mainstem areas) Pool substrate composition <30% sand-silt
	<ul style="list-style-type: none"> Streambed streak marks and/or "banana"-shaped sediment deposits common 	<ul style="list-style-type: none"> Streambed streak marks and/or "banana"-shaped sediment deposits common 	<ul style="list-style-type: none"> Streambed streak marks and/or "banana"-shaped sediment deposits uncommon 	<ul style="list-style-type: none"> Streambed streak marks and/or "banana"-shaped sediment deposits absent
	<ul style="list-style-type: none"> Fresh, large sand deposits very common in channel Moderate to heavy sand deposition along major portion of overbank area 	<ul style="list-style-type: none"> Fresh, large sand deposits common in channel Small localized areas of fresh sand deposits along top of low banks 	<ul style="list-style-type: none"> Fresh, large sand deposits uncommon in channel Small localized areas of fresh sand deposits along top of low banks 	<ul style="list-style-type: none"> Fresh, large sand deposits rare or absent from channel No evidence of fresh sediment deposition on overbank
	<ul style="list-style-type: none"> Point bars present at most stream bends, moderate to large and unstable with high amount of fresh sand 	<ul style="list-style-type: none"> Point bars common, moderate to large and unstable with high amount of fresh sand 	<ul style="list-style-type: none"> Point bars small and stable, well-vegetated and/or armoured with little or no fresh sand 	<ul style="list-style-type: none"> Point bars few, small and stable, well-vegetated and/or armoured with little or no fresh sand
Point range	<input type="checkbox"/> 0 <input type="checkbox"/> 1 <input type="checkbox"/> 2	<input type="checkbox"/> 3 <input type="checkbox"/> 4	<input type="checkbox"/> 5 <input checked="" type="checkbox"/> 6	<input type="checkbox"/> 7 <input type="checkbox"/> 8

Date:	2021-08-19	Reach:	Watercourse 5	Project Code:	21043
Evaluation Category	Poor	Fair	Good	Excellent	
Physical Instream Habitat	<ul style="list-style-type: none"> Wetted perimeter < 40% of bottom channel width (< 45% for large mainstem areas) 	<ul style="list-style-type: none"> Wetted perimeter 40-60% of bottom channel width (45-65% for large mainstem areas) 	<ul style="list-style-type: none"> Wetted perimeter 61-85% of bottom channel width (66-90% for large mainstem areas) 	<ul style="list-style-type: none"> Wetted perimeter > 85% of bottom channel width (> 90% for large mainstem areas) 	
	<ul style="list-style-type: none"> Dominated by one habitat type (usually runs) and by one velocity and depth condition (slow and shallow) (for large mainstem areas, few riffles present, runs and pools dominant, velocity and depth diversity low) 	<ul style="list-style-type: none"> Few pools present, riffles and runs dominant. Velocity and depth generally slow and shallow (for large mainstem areas, runs and pools dominant, velocity and depth diversity intermediate) 	<ul style="list-style-type: none"> Good mix between riffles, runs and pools Relatively diverse velocity and depth of flow 	<ul style="list-style-type: none"> Riffles, runs and pool habitat present Diverse velocity and depth of flow present (i.e., slow, fast, shallow and deep water) 	
	<ul style="list-style-type: none"> Riffle substrate composition: predominantly gravel with high amount of sand < 5% cobble 	<ul style="list-style-type: none"> Riffle substrate composition: predominantly small cobble, gravel and sand 5-24% cobble 	<ul style="list-style-type: none"> Riffle substrate composition: good mix of gravel, cobble, and rubble material 25-49% cobble 	<ul style="list-style-type: none"> Riffle substrate composition: cobble, gravel, rubble, boulder mix with little sand > 50% cobble 	
	<ul style="list-style-type: none"> Riffle depth < 10 cm for large mainstem areas 	<ul style="list-style-type: none"> Riffle depth 10-15 cm for large mainstem areas 	<ul style="list-style-type: none"> Riffle depth 15-20 cm for large mainstem areas 	<ul style="list-style-type: none"> Riffle depth > 20 cm for large mainstem areas 	
	<ul style="list-style-type: none"> Large pools generally < 30 cm deep (< 61 cm for large mainstem areas) and devoid of overhead cover/structure 	<ul style="list-style-type: none"> Large pools generally 30-46 cm deep (61-91 cm for large mainstem areas) with little or no overhead cover/structure 	<ul style="list-style-type: none"> Large pools generally 46-61 cm deep (91-122 cm for large mainstem areas) with some overhead cover/structure 	<ul style="list-style-type: none"> Large pools generally > 61 cm deep (> 122 cm for large mainstem areas) with good overhead cover/structure 	
	<ul style="list-style-type: none"> Extensive channel alteration and/or point bar formation/enlargement 	<ul style="list-style-type: none"> Moderate amount of channel alteration and/or moderate increase in point bar formation/enlargement 	<ul style="list-style-type: none"> Slight amount of channel alteration and/or slight increase in point bar formation/enlargement 	<ul style="list-style-type: none"> No channel alteration or significant point bar formation/enlargement 	
	<ul style="list-style-type: none"> Riffle/Pool ratio 0.49:1 ; $\geq 1.51:1$ 	<ul style="list-style-type: none"> Riffle/Pool ratio 0.5-0.69:1 ; 1.31-1.5:1 	<ul style="list-style-type: none"> Riffle/Pool ratio 0.7-0.89:1 ; 1.11-1.3:1 	<ul style="list-style-type: none"> Riffle/Pool ratio 0.9-1.1:1 	
	<ul style="list-style-type: none"> Summer afternoon water temperature > 27°C 	<ul style="list-style-type: none"> Summer afternoon water temperature 24-27°C 	<ul style="list-style-type: none"> Summer afternoon water temperature 20-24°C 	<ul style="list-style-type: none"> Summer afternoon water temperature < 20°C 	
Point range	<input type="checkbox"/> 0 <input type="checkbox"/> 1 <input type="checkbox"/> 2	<input type="checkbox"/> 3 <input checked="" type="checkbox"/> 4	<input type="checkbox"/> 5 <input type="checkbox"/> 6	<input type="checkbox"/> 7 <input type="checkbox"/> 8	
Water Quality	<ul style="list-style-type: none"> Substrate fouling level: High (> 50%) 	<ul style="list-style-type: none"> Substrate fouling level: Moderate (21-50%) 	<ul style="list-style-type: none"> Substrate fouling level: Very light (11-20%) 	<ul style="list-style-type: none"> Substrate fouling level: Rock underside (0-10%) 	
	<ul style="list-style-type: none"> Brown colour TDS: > 150 mg/L 	<ul style="list-style-type: none"> Grey colour TDS: 101-150 mg/L 	<ul style="list-style-type: none"> Slightly grey colour TDS: 50-100 mg/L 	<ul style="list-style-type: none"> Clear flow TDS: < 50 mg/L 	
	<ul style="list-style-type: none"> Objects visible to depth < 0.15m below surface 	<ul style="list-style-type: none"> Objects visible to depth 0.15-0.5m below surface 	<ul style="list-style-type: none"> Objects visible to depth 0.5-1.0m below surface 	<ul style="list-style-type: none"> Objects visible to depth > 1.0m below surface 	
	<ul style="list-style-type: none"> Moderate to strong organic odour 	<ul style="list-style-type: none"> Slight to moderate organic odour 	<ul style="list-style-type: none"> Slight organic odour 	<ul style="list-style-type: none"> No odour 	
Point range	<input type="checkbox"/> 0 <input type="checkbox"/> 1 <input type="checkbox"/> 2	<input type="checkbox"/> 3 <input type="checkbox"/> 4	<input checked="" type="checkbox"/> 5 <input type="checkbox"/> 6	<input type="checkbox"/> 7 <input type="checkbox"/> 8	
Riparian Habitat Conditions	<ul style="list-style-type: none"> Narrow riparian area of mostly non-woody vegetation 	<ul style="list-style-type: none"> Riparian area predominantly wooded but with major localized gaps 	<ul style="list-style-type: none"> Forested buffer generally > 31 m wide along major portion of both banks 	<ul style="list-style-type: none"> Wide (> 60 m) mature forested buffer along both banks 	
	<ul style="list-style-type: none"> Canopy coverage: <50% shading (30% for large mainstem areas) 	<ul style="list-style-type: none"> Canopy coverage: 50-60% shading (30-44% for large mainstem areas) 	<ul style="list-style-type: none"> Canopy coverage: 60-79% shading (45-59% for large mainstem areas) 	<ul style="list-style-type: none"> Canopy coverage: >80% shading (> 60% for large mainstem areas) 	
Point range	<input type="checkbox"/> 0 <input type="checkbox"/> 1	<input type="checkbox"/> 2 <input type="checkbox"/> 3	<input type="checkbox"/> 4 <input type="checkbox"/> 5	<input checked="" type="checkbox"/> 6 <input type="checkbox"/> 7	
Total overall score (0-42) = 28		Poor (<13)	Fair (13-24)	Good (25-34)	Excellent (>35)

Completed by: _____ Checked by: _____

General Site Characteristics

Project Code: 21043

Date:	2021-08-19	Stream/Reach:	Watercourse 5
Weather:		Location:	Hamilton
Field Staff:	JT DM	Watershed/Subwatershed:	

Features

- Reach break
- Cross-section
- Flow direction
- Riffle
- Pool
- Medial bar
- Eroded bank
- Undercut bank
- Rip rap/stabilization/gabion
- Leaning tree
- Fence
- Culvert/outfall
- Swamp/wetland
- Grasses
- Tree
- Instream log/tree
- Woody debris
- Station location
- Vegetated island

Flow Type

- H1 Standing water
- H2 Scarcely perceptible flow
- H3 Smooth surface flow
- H4 Upwelling
- H5 Rippled
- H6 Unbroken standing wave
- H7 Broken standing wave
- H8 Chute
- H9 Free fall


Substrate

- S1 Silt
- S2 Sand
- S3 Gravel
- S4 Small cobble
- S5 Large cobble
- S6 Small boulder
- S7 Large boulder
- S8 Bimodal
- S9 Bedrock/till

Other

- BM Benchmark
- BS Backsight
- DS Downstream
- WDJ Woody debris jam
- VWC Valley wall contact
- BOS Bottom of slope
- TOS Top of slope
- EP Erosion pin
- RB Rebar
- US Upstream
- TR Terrace
- FC Flood chute
- FP Flood plain
- KP Knick point

Site Sketch:



Additional Notes: Clay silt throughout

- Channel more entrenched upstream
- Minimal flow

Completed by: _____ Checked by: _____

Detailed Assessment (Total Station)

Project Code: 21043

Date:	2021-08-19	Reach:	"Watercourse 5"
Weather:		Location:	Hamilton
Field Staff:	JT DM	Watershed/Subwatershed:	

[illegible]

Survey Direction
<input checked="" type="checkbox"/> Upstream to Downstream
<input type="checkbox"/> Downstream to Upstream

Cross-sections

No. of Cross-sections: _____

Monitoring Cross-sections:

☐ None

☒ Yes

If yes, which ones: 1 & 7

Rain in last 24 hours

☒ None

☐ Yes: Amount _____ mm

Valley Type: Confined Partially Unconfined

Channel Zone: Headwater Transfer Deposition

Land Use: Residential / Ag

Aquatic Vegetation: algae

Portion of Aquatic Vegetation: 10%

Riparian Vegetation: Traces

Extent of Riparian Cover: Fragment None Continuous

Riparian Cover (channel widths): 1-4 4-10 >10

Age Class of Riparian Vegetation: Immature Established Mature
(<5 yrs) (5-30 yrs) (>30 yrs)

Extent of Encroachment: None Minimal Moderate
Heavy Extreme

Density of Woody Debris: Low Moderate High

☒ **Overall Photographs Taken**

Blockage(s) in Channel: Infrastructure Dam LWD

Completed by: _____ Checked By: _____

Page 1 of 1

Cross-Section Characteristics

Project Code: 21043

Date:	2021-08-19	Reach/Cross-section:	X51 - M
Weather:		Location:	Hamilton
Field Staff:	JT DM	Watershed/Subwatershed:	

				Notes
6.30	1622			
6.70	1611			
7.00	1563			
7.30	1526			
7.60	1498			
7.90	1538			
8.10	1555			
8.30	1601			
8.60	1682			
8.90	1783			
9.20	1838			
9.50	1981	BF		
9.60	2095	1		
9.80	2302			
9.90	2340	WC		
10.10	2412			
10.30	2448			
10.50	2432			
10.70	2441			
11.00	2441			
11.30	2400			
11.60	2346			
11.80	2321			
11.95	2295			
12.00	2035			
12.15	2015			
12.30	1873			
12.45	1790			
12.65	1701			
12.90	1638			
13.20	1615			
13.60	1623			
14.00	1630			
14.40	1625			
14.60	1602			
14.85	1600			

Cross-sectional Morphology	
<input type="checkbox"/> Riffle	<input type="checkbox"/> Pool <input checked="" type="checkbox"/> Run <input type="checkbox"/> Other

Substrate	
Sample:	
<input checked="" type="checkbox"/> Bed <input checked="" type="checkbox"/> Bank <input type="checkbox"/> Subpavement <input type="checkbox"/> Water <input type="checkbox"/> None	
Pebble Count (cm):	
1. Clay	11. _____ 21. _____ 31. _____
2. +	12. _____ 22. _____ 32. _____
3. silt	13. _____ 23. _____ 33. _____
4. _____	14. _____ 24. _____ 34. _____
5. _____	15. _____ 25. _____ 35. _____
6. _____	16. _____ 26. _____ 36. _____
7. _____	17. _____ 27. _____ 37. _____
8. _____	18. _____ 28. _____ 38. _____
9. _____	19. _____ 29. _____ 39. _____
10. _____	20. _____ 30. _____ 40. _____
Particle Shape:	
<input type="checkbox"/> Platy <input type="checkbox"/> Sub-angular <input type="checkbox"/> Well Rounded	
<input type="checkbox"/> Very Angular <input type="checkbox"/> Angular <input type="checkbox"/> Sub-Rounded	
<input type="checkbox"/> Rounded	
Embeddedness: _____ %	
Subpavement: _____	
Sorting: <input type="checkbox"/> Well <input type="checkbox"/> Moderate <input type="checkbox"/> Poor <input type="checkbox"/> Very poor	

Sediment Transport	
<input type="checkbox"/> Observed <input checked="" type="checkbox"/> Not Observed	
If Observed:	
<input type="checkbox"/> Suspended <input type="checkbox"/> Sliding <input type="checkbox"/> Rolling <input type="checkbox"/> Saltation	
Percentage of Bed Active: _____ %	

Velocity and Discharge	
Velocity:	Method:
<input checked="" type="checkbox"/> Estimated <u>0</u> m/s	<input type="checkbox"/> Wiffle ball
<input type="checkbox"/> Measured _____ m/s	<input type="checkbox"/> Current Meter
Discharge:	<input type="checkbox"/> ADV
<input type="checkbox"/> Estimated _____ m ³ /s	<input type="checkbox"/> Marsh McBirney
<input type="checkbox"/> Measured _____ m ³ /s	<input type="checkbox"/> Other

Completed by: _____ Checked by: _____

Bank Characteristics

Project Code: 21043

Date:		Reach/XS:	X51
-------	--	-----------	-----

Sketch (Viewed Downstream) Include: vegetation type and location, soil horizons, woody debris, roots, etc.

Left Bank Materials

<input type="checkbox"/> Bedrock	<input type="checkbox"/> Gravel
<input type="checkbox"/> Till	<input type="checkbox"/> Small Cobble
<input type="checkbox"/> Clay	<input type="checkbox"/> Large Cobble
<input type="checkbox"/> Silt	<input type="checkbox"/> Small Boulder
<input type="checkbox"/> Sand	<input type="checkbox"/> Large Boulder

Bank Height: 0.76 m
Bank Angle: 75 °
Root Depth: 0.15 m
Root Density: 50 %
Undercut: 1 m
Erosion Pin: 0.20 m

Penetrometer: _____ kg/cm²
Foot Used: ☐ Yes ☐ No

Right Bank Materials

<input type="checkbox"/> Bedrock	<input type="checkbox"/> Gravel
<input type="checkbox"/> Till	<input type="checkbox"/> Small Cobble
<input type="checkbox"/> Clay	<input type="checkbox"/> Large Cobble
<input type="checkbox"/> Silt	<input type="checkbox"/> Small Boulder
<input type="checkbox"/> Sand	<input type="checkbox"/> Large Boulder

Bank Height: 0.71 m
Bank Angle: 45 °
Root Depth: 0.30 m
Root Density: 20 %
Undercut: 1 m
Erosion Pin: 0.20 m

Penetrometer: _____ kg/cm²
Foot Used: ☐ Yes ☐ No

Additional Notes

Photo Order:

Completed by: _____ Checked by: _____

Page ____ of ____

Project Code: 21043

Page _____ of _____


Bank Characteristics

Project Code: 21043

Date: 2021-08-19

Reach/XS: X52

Sketch (Viewed Downstream) Include: vegetation type and location, soil horizons, woody debris, roots, etc.



Left Bank Materials

- ☐ Bedrock
☐ Till
☒ Clay
☒ Silt
☐ Sand
☐ Gravel
☐ Small Cobble
☐ Large Cobble
☐ Small Boulder
☐ Large Boulder

Bank Height: 0.64 m

Bank Angle: 75 °

Root Depth: 0.30 m

Root Density: 20 %

Undercut: / m

Erosion Pin: m

Penetrometer: kg/cm²Foot Used: ☐ Yes ☐ No

Right Bank Materials

- ☐ Bedrock
☐ Till
☒ Clay
☒ Silt
☐ Sand
☐ Gravel
☐ Small Cobble
☐ Large Cobble
☐ Small Boulder
☐ Large Boulder

Bank Height: 0.78 m

Bank Angle: 80 °

Root Depth: 0.30 m

Root Density: 20 %

Undercut: / m

Erosion Pin: m

Penetrometer: kg/cm²Foot Used: ☐ Yes ☐ No

Additional Notes

Photo Order:

Completed by: _____ Checked by: _____

Page ____ of ____

Cross-Section Characteristics

Project Code: 21043

Date:	2021-08-19	Reach/Cross-section:	X53
Weather:		Location:	Hamilton
Field Staff:	JJ DM	Watershed/Subwatershed:	

[illegible]

Cross-sectional Morphology

☐ Riffle ☐ Pool ☒ Run ☐ Other

Substrate

Sample:

☒ Bed ☒ Bank ☐ Subpavement ☐ Water ☐ None

Pebble Count (cm):

1. _____	11. _____	21. _____	31. _____
2. _____	12. _____	22. _____	32. _____
3. <u>clay</u>	13. _____	23. _____	33. _____
4. <u>+</u>	14. _____	24. _____	34. _____
5. <u>silt</u>	15. _____	25. _____	35. _____
6. _____	16. _____	26. _____	36. _____
7. _____	17. _____	27. _____	37. _____
8. _____	18. _____	28. _____	38. _____
9. _____	19. _____	29. _____	39. _____
10. _____	20. _____	30. _____	40. _____

Particle Shape:

☐ Platy ☐ Sub-angular ☐ Well Rounded
☐ Very Angular ☐ Angular ☐ Sub-Rounded
☐ Rounded

Embeddedness: _____ %

Subpavement: _____

Sorting: ☐ Well ☐ Moderate ☐ Poor ☐ Very poor

Sediment Transport

☐ Observed ☒ Not Observed

If Observed:

☐ Suspended ☐ Sliding ☐ Rolling ☐ Saltation

Percentage of Bed Active: _____ %

Velocity and Discharge

Velocity:

☒ Estimated 0 m/s ☐ Wiffle ball

Method:

☐ Measured _____m/s ☐ Current Meter

Discharge:

☐ Estimated _____ m³/s ☐ Marsh McBirney☐ Measured _____ m³/s ☐ Other _____

Completed by: _____ Checked by: _____


Page ____ of ____

Bank Characteristics

Project Code: 21043

Date: 2021-08-19	Reach/XS: X53
------------------	---------------

Sketch (Viewed Downstream) Include: vegetation type and location, soil horizons, woody debris, roots, etc.



Left Bank Materials

- | | |
|--|--|
| <input type="checkbox"/> Bedrock | <input type="checkbox"/> Gravel |
| <input type="checkbox"/> Till | <input type="checkbox"/> Small Cobble |
| <input type="checkbox"/> Clay | <input type="checkbox"/> Large Cobble |
| <input checked="" type="checkbox"/> Silt | <input type="checkbox"/> Small Boulder |
| <input type="checkbox"/> Sand | <input type="checkbox"/> Large Boulder |

Bank Height: 0.64 m

Bank Angle: 45 °

Root Depth: 0.15 m

Root Density: 40 %

Undercut: 0.03 m

Erosion Pin: m

Penetrometer: kg/cm²Foot Used: ☐ Yes ☐ No

Right Bank Materials

- | | |
|--|--|
| <input type="checkbox"/> Bedrock | <input type="checkbox"/> Gravel |
| <input type="checkbox"/> Till | <input type="checkbox"/> Small Cobble |
| <input checked="" type="checkbox"/> Clay | <input type="checkbox"/> Large Cobble |
| <input checked="" type="checkbox"/> Silt | <input type="checkbox"/> Small Boulder |
| <input type="checkbox"/> Sand | <input type="checkbox"/> Large Boulder |

Bank Height: 0.45 m

Bank Angle: 35 °

Root Depth: 0.15 m

Root Density: 30 %

Undercut: m

Erosion Pin: m

Penetrometer: kg/cm²Foot Used: ☐ Yes ☐ No

Additional Notes

Photo Order: 401R

Completed by: _____ Checked by: _____

Page ____ of ____

Cross-Section Characteristics

Project Code: 21043

Date:	2021-08-19	Reach/Cross-section:	x54
Weather:	26° Sun	Location:	Hamilton
Field Staff:	JT DM	Watershed/Subwatershed:	

[illegible]

Cross-sectional Morphology

☐ Riffle ☐ Pool ☒ Run ☐ Other

Substrate

Sample:

☒ Bed ☒ Bank ☐ Subpavement ☐ Water ☐ None

Pebble Count (cm):

1. clay	11. _____	21. _____	31. _____
2. +	12. _____	22. _____	32. _____
3. 5:17	13. _____	23. _____	33. _____
4. _____	14. _____	24. _____	34. _____
5. _____	15. _____	25. _____	35. _____
6. _____	16. _____	26. _____	36. _____
7. _____	17. _____	27. _____	37. _____
8. _____	18. _____	28. _____	38. _____
9. _____	19. _____	29. _____	39. _____
10. _____	20. _____	30. _____	40. _____

Particle Shape:

☐ Platy ☐ Sub-angular ☐ Well Rounded
☐ Very Angular ☐ Angular ☐ Sub-Rounded
☐ Rounded

Embeddedness: _____ %

Subpavement: _____

Sorting: ☐ Well ☐ Moderate ☐ Poor ☐ Very poor

Sediment Transport

☐ Observed ☒ Not Observed

If Observed:

☐ Suspended ☐ Sliding ☐ Rolling ☐ Saltation

Percentage of Bed Active: _____ %

Velocity and Discharge

Velocity:

☒ Estimated 0 m/s ☐ Wiffle ball

☐ Measured _____ m/s ☐ Current Meter

Discharge:

Discharge: ☐ ADV☐ Estimated _____ m³/s ☐ Marsh McBirney☐ Measured _____ m³/s ☐ Other _____

Completed by: _____ Checked by: _____

Page ____ of ____

Bank Characteristics

Project Code:


21043

Date:

2021-08-19

Reach/XS:

x54

Sketch (Viewed Downstream) Include: vegetation type and location, soil horizons, woody debris, roots, etc.**Left Bank Materials**

- ☐ Bedrock ☐ Gravel
☐ Till ☐ Small Cobble
☒ Clay ☐ Large Cobble
☒ Silt ☐ Small Boulder
☐ Sand ☐ Large Boulder

Bank Height: 0.71 mBank Angle: 85 °Root Depth: 0.30 mRoot Density: 30 %Undercut: / mErosion Pin: / mPenetrometer: _____ kg/cm²Foot Used: ☐ Yes ☐ No**Right Bank Materials**

- ☐ Bedrock ☐ Gravel
☐ Till ☐ Small Cobble
☒ Clay ☐ Large Cobble
☒ Silt ☐ Small Boulder
☐ Sand ☐ Large Boulder

Bank Height: 0.67 mBank Angle: 70 °Root Depth: 0.20 mRoot Density: 10 %Undercut: / mErosion Pin: / mPenetrometer: _____ kg/cm²Foot Used: ☐ Yes ☐ No**Additional Notes****Photo Order:**

Completed by: _____ Checked by: _____

Page ____ of ____

Cross-Section Characteristics

Project Code:

Date:	2021-08-19	Reach/Cross-section:	X55
Weather:	26°C Sun	Location:	Hamilton
Field Staff:	JT PM	Watershed/Subwatershed:	

[illegible]

Cross-sectional Morphology

☐ Riffle ☐ Pool ☒ Run ☐ Other

Substrate

Sample:

☒ Bed ☒ Bank ☐ Subpavement ☐ Water ☐ None

Pebble Count (cm):

1. _____	11. _____	21. _____	31. _____
2. <u>clay</u>	12. _____	22. _____	32. _____
3. <u>+</u>	13. _____	23. _____	33. _____
4. <u>Silt</u>	14. _____	24. _____	34. _____
5. _____	15. _____	25. _____	35. _____
6. _____	16. _____	26. _____	36. _____
7. _____	17. _____	27. _____	37. _____
8. _____	18. _____	28. _____	38. _____
9. _____	19. _____	29. _____	39. _____
10. _____	20. _____	30. _____	40. _____

Particle Shape:

☐ Platy ☐ Sub-angular ☐ Well Rounded
☐ Very Angular ☐ Angular ☐ Sub-Rounded
☐ Rounded

Embededness: _____ %

Subpavement: _____

Sorting: ☐ Well ☐ Moderate ☐ Poor ☐ Very poor

Sediment Transport

☐ Observed ☒ Not Observed

If Observed:

☐ Suspended ☐ Sliding ☐ Rolling ☐ Saltation

Percentage of Bed Active: _____ %

Velocity and Discharge

Velocity:

Method:

☒ Estimated 0 m/s ☐ Wiffle ball

☐ Wiffle ball☐ Measured m/s☐ Current Meter

Discharge:

☐ ADV☐ Estimated m^3/s

☐ Marsh McBirney

☐ Measured m^3/s ☐ Other

Completed by: _____ Checked by: _____


Page ____ of ____

Bank Characteristics

Project Code: 21048

Date:

Reach/XS:

Sketch (Viewed Downstream) Include: vegetation type and location, soil horizons, woody debris, roots, etc.**Left Bank Materials**

- ☐ Bedrock ☐ Gravel
☐ Till ☐ Small Cobble
☒ Clay ☐ Large Cobble
☒ Silt ☐ Small Boulder
☐ Sand ☐ Large Boulder

Bank Height: 0.40 m

Bank Angle: 30 °

Root Depth: 0.10 m

Root Density: 40 %

Undercut: / m

Erosion Pin: / m

Penetrometer: _____ kg/cm²Foot Used: ☐ Yes ☐ No**Right Bank Materials**

- ☐ Bedrock ☐ Gravel
☐ Till ☐ Small Cobble
☒ Clay ☐ Large Cobble
☒ Silt ☐ Small Boulder
☐ Sand ☐ Large Boulder

Bank Height: 0.46 m

Bank Angle: 30 °

Root Depth: 0.10 m

Root Density: 10 %

Undercut: / m

Erosion Pin: / m

Penetrometer: _____ kg/cm²Foot Used: ☐ Yes ☐ No**Additional Notes****Photo Order:**

Completed by: _____ Checked by: _____

Page ____ of ____

Cross-Section Characteristics

Project Code:

21043

Date:	2021-08-19	Reach/Cross-section:	XSG
Weather:	26°C Sun	Location:	Hamilton
Field Staff:	JT PM	Watershed/Subwatershed:	

[illegible]

Cross-sectional Morphology

☐ Riffle ☐ Pool ☒ Run ☐ Other

Substrate

Sample:

☒ Bed ☒ Bank ☐ Subpavement ☐ Water ☐ None

Pebble Count (cm):

1. _____	11. _____	21. _____	31. _____
2. _____	12. _____	22. _____	32. _____
3. <u>Clay</u>	13. _____	23. _____	33. _____
4. <u>+</u>	14. _____	24. _____	34. _____
5. <u>Silt</u>	15. _____	25. _____	35. _____
6. _____	16. _____	26. _____	36. _____
7. _____	17. _____	27. _____	37. _____
8. _____	18. _____	28. _____	38. _____
9. _____	19. _____	29. _____	39. _____
10. _____	20. _____	30. _____	40. _____

Particle Shape:

☐ Platy ☐ Sub-angular ☐ Well Rounded
☐ Very Angular ☐ Angular ☐ Sub-Rounded
☐ Rounded

Embeddedness: _____ %

Subpavement: _____

Sorting: ☒ Well ☐ Moderate ☐ Poor ☐ Very poor

Sediment Transport

☐ Observed ☒ Not Observed

If Observed:

☐ Suspended ☐ Sliding ☐ Rolling ☐ Saltation

Percentage of Bed Active: _____ %

Velocity and Discharge

Velocity:

☒ Estimated 0 m/s ☐ Wiffle ball☐ Measured _____ m/s ☐ Current Meter

Discharge:

☐ ADV☐ Estimated _____ m³/s ☐ Marsh McBirney☐ Measured _____ m³/s ☐ Other _____

Completed by: _____ Checked by: _____

Page ____ of ____

Bank Characteristics

Project Code: 21043


Date:

2021-08-19

Reach/XS:

XS6

Sketch (Viewed Downstream) Include: vegetation type and location, soil horizons, woody debris, roots, etc.



Left Bank Materials

- ☐ Bedrock ☐ Gravel
☐ Till ☐ Small Cobble
☒ Clay ☐ Large Cobble
☒ Silt ☐ Small Boulder
☐ Sand ☐ Large Boulder

Bank Height: 0.56 m

Bank Angle: 70 °

Root Depth: 0.40 m

Root Density: %

Undercut: m

Erosion Pin: m

Penetrometer: kg/cm²Foot Used: ☐ Yes ☐ No

Right Bank Materials

- ☐ Bedrock ☐ Gravel
☐ Till ☐ Small Cobble
☒ Clay ☐ Large Cobble
☒ Silt ☐ Small Boulder
☐ Sand ☐ Large Boulder

Bank Height: 0.78 m

Bank Angle: 75 °

Root Depth: 0.40 m

Root Density: %

Undercut: m

Erosion Pin: m

Penetrometer: kg/cm²Foot Used: ☐ Yes ☐ No

Additional Notes

Photo Order:

WDLR

Completed by: _____ Checked by: _____

Page ____ of ____

Cross-Section Characteristics

Project Code: 21043

Date:	2021-08-19	Reach/Cross-section:	X57
Weather:	26° Sun	Location:	Hamilton
Field Staff:	JT	Watershed/Subwatershed:	

[illegible]

Cross-sectional Morphology

☐ Riffle ☐ Pool ☒ Run ☐ Other

Substrate

Sample:

☐ Bed ☐ Bank ☐ Subpavement ☐ Water ☐ None

Pebble Count (cm):

1. _____ 11. _____ 21. _____ 31. _____

2. _____ 12. _____ 22. _____ 32. _____

3. _____ 13. _____ 23. _____ 33. _____

4. Clay 14. 24. 34.

5. 1 15. 1 25. 1 35. 1

6. silt 16. _____ 26. _____ 36. _____

7. _____ 17. _____ 27. _____ 37. _____

8. 18. 28. 38.

9. _____ 19. _____ 29. _____ 39. _____

10. _____ 20. _____ 30. _____ 40. _____

Particle Shape:

☐ Platy ☐ Sub-angular ☐ Well Rounded☐ Very Angular ☐ Angular ☐ Sub-Rounded☐ Rounded

Embeddedness: _____ %

Subpavement: _____

Sorting: ☐ Well ☐ Moderate ☐ Poor ☐ Very poor

Sediment Transport

☐ Observed ☒ Not Observed

If Observed:

☐ Suspended ☐ Sliding ☐ Rolling ☐ Saltation

Percentage of Bed Active: _____ %

Velocity and Discharge

Velocity:

☒ Estimated 0 m/s ☐ Wiffle ball☐ Measured _____ m/s ☐ Current Meter

Discharge:

☐ ADV☐ Estimated _____ m³/s ☐ Marsh McBirney☐ Measured ☐ m³/s ☐ Other

Completed by: _____ Checked by: _____


Page ____ of ____

Bank Characteristics

Project Code: _____

Date: _____

Reach/XS: _____

Sketch (Viewed Downstream) Include: vegetation type and location, soil horizons, woody debris, roots, etc.**Left Bank Materials**

- | | |
|--|--|
| <input type="checkbox"/> Bedrock | <input type="checkbox"/> Gravel |
| <input type="checkbox"/> Till | <input type="checkbox"/> Small Cobble |
| <input checked="" type="checkbox"/> Clay | <input type="checkbox"/> Large Cobble |
| <input checked="" type="checkbox"/> Silt | <input type="checkbox"/> Small Boulder |
| <input type="checkbox"/> Sand | <input type="checkbox"/> Large Boulder |

Bank Height: 0.62 m
 Bank Angle: 80 °
 Root Depth: 0.40 m
 Root Density: 60 %
 Undercut: / m
 Erosion Pin: 0.20 m

Penetrometer: _____ kg/cm²Foot Used: ☐ Yes ☐ No**Right Bank Materials**

- | | |
|--|--|
| <input type="checkbox"/> Bedrock | <input type="checkbox"/> Gravel |
| <input type="checkbox"/> Till | <input type="checkbox"/> Small Cobble |
| <input checked="" type="checkbox"/> Clay | <input type="checkbox"/> Large Cobble |
| <input checked="" type="checkbox"/> Silt | <input type="checkbox"/> Small Boulder |
| <input type="checkbox"/> Sand | <input type="checkbox"/> Large Boulder |

Bank Height: 0.64 m
 Bank Angle: 70 °
 Root Depth: 0.40 m
 Root Density: 15 %
 Undercut: / m
 Erosion Pin: 0.20 m

Penetrometer: _____ kg/cm²Foot Used: ☐ Yes ☐ No**Additional Notes****Photo Order:**

Completed by: _____ Checked by: _____

Page ____ of ____

Cross-Section Characteristics

Project Code: 21043

Date:	2021-08-19	Reach/Cross-section:	XS 8
Weather:	26° Sun	Location:	Hamilton
Field Staff:	JT DM	Watershed/Subwatershed:	

[illegible]

Cross-sectional Morphology

☐ Riffle ☐ Pool ☒ Run ☐ Other

Substrate

Sample:

☒ Bed ☒ Bank ☐ Subpavement ☐ Water ☐ None

Pebble Count (cm):

1. _____	11. _____	21. _____	31. _____
2. _____	12. _____	22. _____	32. _____
3. _____	13. _____	23. _____	33. _____
4. _____	14. _____	24. _____	34. _____
5. _____	15. _____	25. _____	35. _____
6. _____	16. _____	26. _____	36. _____
7. _____	17. _____	27. _____	37. _____
8. _____	18. _____	28. _____	38. _____
9. _____	19. _____	29. _____	39. _____
10. _____	20. _____	30. _____	40. _____

Particle Shape:

☐ Platy ☐ Sub-angular ☐ Well Rounded
☐ Very Angular ☐ Angular ☐ Sub-Rounded
☐ Rounded

Embeddedness: %

Subpavement: _____

Sorting: ☐ Well ☐ Moderate ☐ Poor ☐ Very poor

Sediment Transport

☐ Observed ☒ Not Observed

If Observed:

☐ Suspended ☐ Sliding ☐ Rolling ☐ Saltation

Percentage of Bed Active: _____ %

Velocity and Discharge

Velocity:

☒ Estimated 0 m/s ☐ Wiffle ball

Method:

☐ Wiffle ball☐ Measured _____ m/s ☐ Current Meter

Discharge:

☐ ADV☐ Estimated _____ m³/s ☐ Marsh McBirney☐ Measured _____ m³/s ☐ Other _____

Completed by: _____ Checked by: _____

Page ____ of ____


Bank Characteristics

Project Code: 21043

Date: 2021-08-19

Reach/XS: XS8

Sketch (Viewed Downstream) Include: vegetation type and location, soil horizons, woody debris, roots, etc.



Left Bank Materials

- ☐ Bedrock ☐ Gravel
☐ Till ☐ Small Cobble
☒ Clay ☐ Large Cobble
☒ Silt ☐ Small Boulder
☐ Sand ☐ Large Boulder

Bank Height: 0.54 m
 Bank Angle: 50 °
 Root Depth: 0.30 m
 Root Density: 20 %
 Undercut: / m
 Erosion Pin: / m

Penetrometer: _____ kg/cm²Foot Used: ☐ Yes ☐ No

Right Bank Materials

- ☐ Bedrock ☐ Gravel
☐ Till ☐ Small Cobble
☒ Clay ☐ Large Cobble
☒ Silt ☐ Small Boulder
☐ Sand ☐ Large Boulder

Bank Height: 0.51 m
 Bank Angle: 30 °
 Root Depth: 0.30 m
 Root Density: 20 %
 Undercut: / m
 Erosion Pin: / m

Penetrometer: _____ kg/cm²Foot Used: ☐ Yes ☐ No

Additional Notes

Photo Order:

4DLR

Completed by: _____ Checked by: _____

Page ____ of ____


Bank Characteristics

Project Code: 21043

Date: 2021-08-19

Reach/XS: XS8

Sketch (Viewed Downstream) Include: vegetation type and location, soil horizons, woody debris, roots, etc.



Left Bank Materials

- ☐ Bedrock
☐ Till
☒ Clay
☒ Silt
☐ Sand
☐ Gravel
☐ Small Cobble
☐ Large Cobble
☐ Small Boulder
☐ Large Boulder

Bank Height: 0.54 m
 Bank Angle: 50 °
 Root Depth: 0.30 m
 Root Density: 20 %
 Undercut: / m
 Erosion Pin: / m

Penetrometer: kg/cm²Foot Used: ☐ Yes ☐ No

Right Bank Materials

- ☐ Bedrock
☐ Till
☒ Clay
☒ Silt
☐ Sand
☐ Gravel
☐ Small Cobble
☐ Large Cobble
☐ Small Boulder
☐ Large Boulder

Bank Height: 0.51 m
 Bank Angle: 30 °
 Root Depth: 0.30 m
 Root Density: 20 %
 Undercut: / m
 Erosion Pin: / m

Penetrometer: kg/cm²Foot Used: ☐ Yes ☐ No

Additional Notes

Photo Order:

4DLR

Completed by: _____ Checked by: _____

Page ____ of ____



Appendix D

Detailed Assessment Summary

Detailed Geomorphological Assessment Summary

Reach: Watercourse 5

Project Number:	PN21043	Date:	2021-08-19
Client:	Urbantech Consulting	Length Surveyed (m):	86.1
Location:	Hamilton	# of Cross-Sections:	8

Reach Characteristics

Drainage Area:	167.1 ha	Dominant Riparian Vegetation Type:	Trees
Geology/Soils:	Paleozoic Bedrock	Extent of Riparian Cover:	Continuous
Surrounding Land Use:	Residential/Agricultural	Width of Riparian Cover:	4-10 Channel Widths
Valley Type:	Unconfined	Age Class of Riparian Vegetation:	Established (5-30 Years)
Dominant Instream Vegetation Type:	Algae	Extent of Encroachment into Channel:	Minimal
Portion of Reach with Vegetation:	10%	Density of Woody Debris:	Low

Hydrology

Measured Discharge (m³/s):	Not measured	Calculated Bankfull Discharge (m³/s):	1.31
Modelled 2-year Discharge (m³/s):	Not modelled	Calculated Bankfull Velocity (m/s):	1.06
Modelled 2-year Velocity (m/s):	Not modelled		


Profile Characteristics

Bankfull Gradient (%):	0.76
Channel Bed Gradient (%):	0.42
Riffle Gradient (%):	n/a
Riffle Length (m):	n/a
Riffle-Pool Spacing (m):	n/a

Planform Characteristics

Sinuosity:	1.29
Meander Belt Width (m):	Not measured
Radius of Curvature (m):	Not measured
Meander Amplitude (m):	Not measured
Meander wavelength (m):	Not measured

Longitudinal Profile




Bank Characteristics

	Minimum	Maximum	Average		Minimum	Maximum	Average
Bank Height (m):	0.40	0.78	0.62				
Bank Angle (deg):	30	85	64	Torvane Value (kg/cm²):	Not measured		
Root Depth (m):	0.10	0.40	0.27	Penetrometer Value (kg/cm³):	Not measured		
Root Density (%):	10	60	28	Bank Material (range):	Silty-clay loam (uniform)		
Bank Undercut (m):	0.00	0.03	0.00				

Cross-Sectional Characteristics


	Minimum	Maximum	Average
Bankfull Width (m):	2.60	5.00	3.64
Average Bankfull Depth (m):	0.13	0.42	0.34
Bankfull Width/Depth (m/m):	7	38	13
Wetted Width (m):	0.10	1.80	1.22
Average Water Depth (m):	0.01	0.11	0.05
Wetted Width/Depth (m/m):	4	60	28
Entrenchment (m):	Not measured		
Entrenchment Ratio (m/m):	Not measured		
Maximum Water Depth (m):	0.04	0.20	0.11
Manning's n :	0.040		



Photograph at cross section 6 (looking downstream)

Representative Cross-Section #6

Cross Section 6



Substrate Characteristics

Particle Size (mm)

D_{10} :	<2
D_{50} :	<2
D_{84} :	<2

Subpavement:

Shale

Particle shape:

N/A

Embeddedness (%):

N/A


Particle range (riffle):

Silt to clay


Particle Range (pool):

Silt to clay

Cumulative Particle Size Distribution



Channel Thresholds			
Flow Competency (m/s):		Tractive Force at Bankfull (N/m ²):	25.33
for D ₅₀ :	n/a	Tractive Force at 2-year flow (N/m ²):	Not modelled
for D ₈₄ :	n/a	Critical Shear Stress (D ₅₀) (N/m ²):	n/a
Unit Stream Power at Bankfull (W/m ²):			26.86


General Field Observations
<div>Channel Description</div> <p>Watercourse 5 flows through an unconfined valley surrounded by a mix of residential and agricultural areas. The continuous extent of riparian vegetation consists of grasses, herbaceous vegetation, shrubs, and trees. This vegetation is established on the landscape and only minimally encroaches upon the channel. The average bankfull width and depth are 3.64 m and 0.34 m, respectively. Both the bed and bank material is comprised primarily of a compact silty clay loam, with trace amounts of shale pebbles observed. No riffle-pool sequeces are present within the reach. The channel generally exhibits a trapezoidal cross-section shape, with bank angles ranging from 30 to 85. Undercutting and active erosion of the banks was not prevelant. Flow velocities were imperceptible during the assessment.</p> <div>Photo of typical channel conditions, facing upstream</div> 




Appendix E


Erosion Modelling Hydrographs

**WC5
25 mm
event**




**WC5
2-year
event**









**WC5
25-year
event**



**WC5
50-year
event**







GENERAL NOTES

1. THE APPROPRIATING CHANNEL REALIGNMENT TECHNICAL DESIGN BRIEF PREPARED BY GEO MORPHIX LTD. (2023) PROVIDES ADDITIONAL DESIGN DETAILS AND DIRECTION FOR IMPLEMENTATION AND IS TO BE REVIEWED IN CONJUNCTION WITH THE DESIGN DOCUMENTS.

2. ALL CONTRACT DRAWINGS, SPECIFICATIONS AND APPLICABLE PERMITS MUST BE KEPT ON SITE DURING CONSTRUCTION AND AVAILABLE FOR REFERENCE.

3. THE CONTRACTOR MUST NOTIFY THE DESIGNER AND CONTRACT ADMINISTRATOR OF THE INTENT TO COMMENCE CONSTRUCTION 48 HOURS PRIOR TO THE START OF CONSTRUCTION.

4. THE CONTRACTOR IS RESPONSIBLE FOR ALL UTILITY LOCATIONS.

5. LAYOUT MUST BE REVIEWED AND APPROVED BY THE DESIGNER/ DESIGNER REPRESENTATIVE, DESIGNATED BY THE CONTRACT ADMINISTRATION, PRIOR TO THE START OF CONSTRUCTION.

6. CONSTRUCTION OBSERVATION IS TO BE PERFORMED BY A CERTIFIED FLUVAL, GEOMORPHOLOGIST OR ENVIRONMENTAL INSPECTOR EMPLOYED BY THE CONTRACTOR UNDER DIRECTION FROM THE DESIGNER.

7. ON-SITE SUPPORT FROM PROJECT ENGINEER (E.G. GEOTECHNICAL, HYDROLOGICAL, AND/OR WATER QUALITY) ENGINEER, EMPLOYED BY THE CONTRACTOR, IS REQUIRED TO MONITOR AND RECORD CONSTRUCTION CONDITIONS TO SUPPORT CHANNEL REALIGNMENT CONSTRUCTION.

8. THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS, WITHOUT THIS PERMISSION, WAIVER, OR THE OPINION OF THE AUTHORITY, THE CONDITIONS OF THE PERMIT ARE NOT BEING COMPLIED WITH. THIS APPROVAL DOES NOT EXEMPT THE PROPERTY OWNER/APPLICANT/AGENCY FROM THE PROVISIONS OF ANY OTHER FEDERAL, STATE, OR MUNICIPAL LAWS, ORDINANCES, RULES, OR RIGHTS UNDER COMMON LAW.

TIMING OF WORKS

1. WORKS SHALL BE COMPLETED DURING THE DESIGNATED IN-WATER WORKS WINDOW SET OUT BY MNRF/DFO.
2. TREE CLEARING IS TO BE COMPLETED OUTSIDE THE BIRD NESTING SEASON (APRIL 1ST TO AUGUST 1ST) TO
COMPLY WITH THE FEDERAL MIGRATORY BIRDS CONVENTION ACT. ANY TREES THAT REQUIRE REMOVAL OUTSIDE
OF THE TIMING WINDOW MUST FIRST BE INSPECTED BY A QUALIFIED BIOLOGIST TO DETERMINE THE PRESENCE OF
NESTING BIRDS.
3. THE WEATHER FORECAST SHOULD BE CONTINUALLY MONITORED TO ENSURE THAT WORKS ARE UNDERTAKEN
ONLY DURING FAVOURABLE WEATHER CONDITIONS.
4. COMPLETE THE WORKS WITH MINIMAL AVOIDABLE INTERRUPTIONS ONCE THEY COMMENCE.

SITE AND MATERIAL MANAGEMENT

1. ALL CONSTRUCTION EQUIPMENT AND MATERIALS (IMPORTED OR EXCAVATED) MUST BE STORED AT LEAST 30 m AWAY FROM ANY WATERBODY IN A STABLE AREA ABOVE THE ACTIVE FLOODPLAIN, OR IN A DESIGNATED STORAGE AREA.
2. IN THE EVENT OF AN UNEXPECTED STORM, ALL UNLOADED ITEMS THAT HAVE THE POTENTIAL TO CAUSE A SPILL OR AN OBSTACLE TO FLOODING MUST BE MOVED TO A STABLE AREA ABOVE THE ACTIVE FLOODPLAIN.
3. STOCKPILES MUST BE LOCATED OUTSIDE THE EXTRACTED WATERSHED.
4. STABILIZE, TEMPORARILY OR PERMANENTLY, ANY DISTURBED AREAS ON WORK PROGRESSES, OR SOON AS POSSIBLE.
5. MINIMIZE THE AREA OF DISTURBANCE TO THE EXTENT POSSIBLE. ALL DISTURBED GROUND LEFT NACTIVE FOR 30 DAYS MUST BE REVEGETATED WITH THE SAME SPECIES AND SEED MIX AS THE UNDISTURBED AREAS.
6. APPROPRIATE SEED MIX AS NOTED WITHIN THE FINAL APPROVED RESTORATION PLAN.
7. ALL EROSION, SEDIMENT, AND SLOPE STABILIZATION MEASURES MUST BE PROTECTED AND DELINEATED WITH CONSTRUCTION FENCING OR PROTECTION BARRIERS.
8. ALL GRADES IN THE AREA REGULATED BY THE CONSERVATION AUTHORITY MUST BE MAINTAINED OR MATCHED.
9. ALL OTHERS: AT THE DISCRETION OF THE CONSERVATION AUTHORITY.
10. AN AFTER-HOURS CONTACT NUMBER IS TO BE VISIBLY POSTED ONSITE FOR EMERGENCIES. ALL THE PLANS AND SPECIFICATIONS MUST BE KEPT ON SITE AT ALL TIMES.

EROSION AND SEDIMENT CONTROL


1. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSTALLED PRIOR TO START OF WORK.
2. FOLLOWING INSTALLATION OF THE PROPOSED EROS MEASURES, A QUALIFIED AGENT OF THE PROPONENT (E.G. CA-CRREG CERTIFIED MONITOR) WILL CONDUCT REGULAR SITE VISITS TO MONITOR ALL WORKS, PARTICULARLY THE OPERATION OF THE EROSION AND SEDIMENT CONTROL MEASURES, AND IN-OR-HOLD WORKS.
3. ERASE THE ENVIRONMENTAL MONITOR WILL CONTACT THE PROPONENT, THE CONSERVATION AUTHORITY, AND THE CONTRACT ADMINISTRATOR IMMEDIATELY UPON IDENTIFICATION OF ANY VIOLATIONS.
4. EROSION AND SEDIMENT CONTROLS MUST BE MAINTAINED DURING CONSTRUCTION, AND ANY REQUIRED REPAIRS TO EROSION AND SEDIMENT CONTROLS MUST BE COMPLETED WITHIN 24 HOURS AFTER THEY HAVE BEEN IDENTIFIED DURING THE MONITORING.
5. EROSION AND SEDIMENT CONTROLS MAY REQUIRE PERIODIC ADJUSTMENTS TO REFLECT CHANGING SITE CONDITIONS. THE MONITOR WILL BE THE ONLY PERSON WHO WILL BE AUTHORIZED TO MAKE SUCH ADJUSTMENTS TO THE FUNCTION.
6. VIOLATIONS TO THE EROSION AND SEDIMENT CONTROL PLAN BEYOND MINOR ADJUSTMENTS MUST BE APPROVED BY THE CONTRACT ADMINISTRATOR.
7. ADDITIONAL EROSION AND SEDIMENT CONTROL SUPPLIES MUST BE KEPT ON SITE IN ORDER TO FACILITATE IMMEDIATE REPAIRS AND UPGRADES.
8. ALL TEMPORARY SEDIMENT CONTROLS MUST BE REMOVED AFTER THE CONTRACT ADMINISTRATOR DEEMS THE SITE READY FOR REMOVAL OF THE EROSION AND SEDIMENT CONTROLS.
9. THE PROJECT PROPONENT OR THEIR REPRESENTATIVE IS ULTIMATELY RESPONSIBLE FOR CONTROLLING EROSION AND SEDIMENTATION. THE CONTRACT ADMINISTRATOR WILL NOT BE RESPONSIBLE FOR EROSION OR SEDIMENTATION IF EXCESSIVE EROSION RESULTS FROM THE CONSTRUCTION ACTIVITIES. THE ONSITE SUPERVISOR/INSPECTOR AND/OR THE LOCAL REGULATORY BODY RESERVE THE RIGHT TO REQUEST ADDITIONAL EROS MEASURES WHICH MAY BE REQUIRED TO PROTECT THE ENVIRONMENT.

DELETERIOUS SUBSTANCE CONTROL/SPILL MANAGEMENT

1. PREVENT THE RELEASE OF SEDIMENT, SEDIMENT-LADEN WATER, RAW CONCRETE, CONCRETE LEACHATE OR ANY OTHER DELETERIOUS SUBSTANCES INTO ANY WATERBODY, RAYNE OR STORM SEWER SYSTEM.
2. ENSURE EQUIPMENT AND MACHINERY ARE IN GOOD OPERATING CONDITION (POWER WASHED), FREE OF LEAKS, AND OIL AND GREASE FREE.
3. NO EQUIPMENT REFUELLING OR SERVICING SHOULD BE UNDERTAKEN WITHIN 30 m OF ANY WATERCOURSE OR SURFACE WATER DRAINAGE.
4. A SPILL CONTAINMENT KIT MUST BE READILY ACCESSIBLE ON SITE IN THE EVENT OF A RELEASE OF A DELETERIOUS SUBSTANCE TO THE ENVIRONMENT. ON-SITE STAFF MUST BE TRAINED IN ITS USE.
5. THE CONTRACT ADMINISTRATOR MUST BE NOTIFIED IMMEDIATELY IN THE EVENT OF A SPILL OF DELETERIOUS SUBSTANCE. ANY SEDIMENT SPILL FROM THE SITE SHOULD BE REPORTED TO MINISTRY OF ENVIRONMENT (SPILL RESPONSE TEAM).

WORK AREA ISOLATION



1. ALL WORK IN ISOLATED WORK AREAS MUST BE COMPLETED IN THE DAY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
 2. CROSSING AN ACTIVE WATERCOURSE OR WETLAND BY EQUIPMENT, VEHICLES, PERSONNEL, ETC. IS NOT PERMITTED UNLESS APPROVED BY THE CONSERVATION AUTHORITY. ALL ACCESS TO WORK SITES SHALL BE FROM EITHER SIDES OF THE WATERCOURSE OR WETLAND.
 3. WHEN ENTERING DENSE VEGETATIVE GROUNDCOVER, THE DISCHARGE MUST BE LOCATED AT LEAST 30 M FROM ANY WATERCOURSE OR WETLAND IN AN AREA WITH DENSE VEGETATIVE GROUNDCOVER, AND WHERE THE DISCHARGE CAN RETURN TO THE WATERBODY DOWNSTREAM OF THE WORK AREA OVER THE GROUNDCOVER.
- THE REMEDIATION OF THE WORK AREA ONCE ISOLATED, FISH HAVEN MUST BE COMPLETED BY A QUALIFIED TECHNICIAN WITH A LICENSE FROM THE ONTARIO MINISTRY OF NATURAL RESOURCES AND FORESTRY.



BLOCK 1 BSS
FRUITLAND-WINONA BLOCK 1 OWNERS
GROUP, HAMILTON

WATERCOURSE 5
CONCEPTUAL CHANNEL DESIGN
PLANFORM AND PROFILE

PROJECT No.: 21043	DRAWING No.: GEO-1
SCALE: AS NOTED	SHEET 1 OF 5



- GENERAL NOTES
- THE ACCOMPANYING CHANNEL REALIGNMENT TECHNICAL DESIGN BRIEF PREPARED BY GEO MORPHIX LTD. (2023) PROVIDES ADDITIONAL DESIGN DETAILS AND DIRECTION FOR IMPLEMENTATION AND IS TO BE REVIEWED IN CONJUNCTION WITH THIS DRAWING SET.
 - ALL CONTRACT DRAWINGS, SPECIFICATIONS AND APPLICABLE PERMITS MUST BE KEPT ON SITE DURING CONSTRUCTION FOR REFERENCE.
 - THE CONTRACTOR MUST NOTIFY THE DESIGNER AND CONTRACT ADMINISTRATOR OF THE INTENT TO COMMENCE WORK AT LEAST 48 HOURS IN ADVANCE.
 - THE CONTRACTOR IS RESPONSIBLE FOR ALL UTILITY LOCATES.
 - LAYOUT MUST BE REVIEWED AND APPROVED BY THE DESIGNER / DESIGNER REPRESENTATIVE, DESIGNATED ENGINEER, AND THE CONTRACT ADMINISTRATOR.
 - CONSTRUCTION OBSERVATION IS TO BE PERFORMED BY A CERTIFIED FLUVIAL GEOMORPHOLOGIST OR EXPERIENCED ENVIRONMENTAL INSPECTOR UNDER DIRECTION FROM THE DESIGNER.
 - ON-SITE SUPPORT FROM PROJECT ENGINEER (E.G. GEOTECHNICAL, HYDROGEOLOGICAL, AND/OR WATER RESOURCES ENGINEER) REQUIRED TO ASSESS AND ENSURE FAVOURABLE SURFICIAL AND SUBSURFACE CONDITIONS TO SUPPORT CHANNEL REALIGNMENT CONSTRUCTION.
 - BE ADVISED THAT THE LOCAL REGULATORY BODY MAY, AT ANY TIME, WITHDRAW THIS PERMISSION, IF, IN THE OPINION OF THE AUTHORITY, THE CONDITIONS OF THE PERMIT ARE NOT BEING COMPLIED WITH. THIS APPROVAL DOES NOT EXEMPT THE PROPERTY OWNER/APPLICANT/AGENT FROM THE PROVISIONS OF ANY OTHER FEDERAL, PROVINCIAL OR MUNICIPAL STATUTES, REGULATIONS OR BY-LAWS, OR ANY RIGHTS UNDER COMMON LAW.

- TIMING OF WORKS
- WORKS SHALL BE COMPLETED DURING THE DESIGNATED IN-WATER WORKS WINDOW SET OUT BY MNRF/DO.
 - TREE CLEARING IS TO BE COMPLETED OUTSIDE THE BIRD NESTING SEASON (APRIL 1ST TO AUGUST 1ST) TO COMPLY WITH THE FEDERAL MIGRATORY BIRDS CONVENTION ACT. ANY TREES THAT REQUIRE REMOVAL OUTSIDE OF THIS TIMING WINDOW MUST FIRST BE INSPECTED BY A QUALIFIED BIOLOGIST TO DETERMINE THE PRESENCE OF NESTING BIRDS.
 - THE WEATHER FORECAST SHOULD BE CONTINUALLY MONITORED TO ENSURE THAT WORKS ARE UNDERTAKEN ONLY DURING FAVOURABLE WEATHER CONDITIONS.
 - COMPLETE THE WORKS WITH MINIMAL AVOIDABLE INTERRUPTIONS ONCE THEY COMMENCE.

- SITE AND MATERIAL MANAGEMENT
- ALL CONSTRUCTION EQUIPMENT AND MATERIALS (IMPORTED OR EXCAVATED) MUST BE STORED AT LEAST 30 m AWAY FROM ANY WATERBODY IN A STABLE AREA ABOVE THE ACTIVE FLOODPLAIN OR IN A DESIGNATED STAGING/STORAGE AREA.
 - IN THE EVENT OF AN UNEXPECTED STORM, ALL UNFIXED ITEMS THAT HAVE THE POTENTIAL TO CAUSE A SPILL OR AN OBSTRUCTION TO FLOW MUST BE MOVED A STABLE AREA ABOVE ACTIVE FLOODPLAIN.
 - STOCKPILES MUST BE LOCATED OUTSIDE THE ISOLATED WORK AREAS.
 - STABILIZE, TEMPORARILY OR PERMANENTLY, ANY DISTURBED AREAS AS WORK PROGRESSES, OR SOON AS CONDITIONS ALLOW.
 - MINIMIZE THE AREA OF DISTURBANCE TO THE EXTENT POSSIBLE. ALL DISTURBED GROUND LEFT INACTIVE FOR MORE THAN 30 DAYS SHALL BE STABILIZED USING APPROPRIATE EROSION CONTROL MEASURES AND AN APPROPRIATE SEED MIX AS NOTED WITHIN THE FINAL APPROVED RESTORATION PLAN.
 - ALL VEGETATION, ADJACENT TO THE WORK AREA, MUST BE PROTECTED AND DELINEATED WITH CONSTRUCTION FENCING OR TREE PROTECTION BARRIERS.
 - ALL GRADES IN THE AREA REGULATED BY THE CONSERVATION AUTHORITY MUST BE MAINTAINED OR MATCHED, UNLESS OTHERWISE AUTHORIZED IN THE APPLICABLE PERMIT.
 - AN AFTER-HOURS CONTACT NUMBER IS TO BE VISIBLY POSTED ON-SITE FOR EMERGENCIES. ALL THE PLANS SHOULD HAVE NAME AND CONTACT INFO OF THE PERSON RESPONSIBLE FOR ESC MEASURES.




- EROSION AND SEDIMENT CONTROL
- ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSTALLED PRIOR TO START OF WORKS. FOLLOWING INSTALLATION OF THE PROPOSED ESC MEASURES, A QUALIFIED AGENT OF THE PROPONENT (E.G. CAN-CISEC CERTIFIED MONITOR) WILL CONDUCT REGULAR SITE VISITS TO MONITOR ALL WORKS, PARTICULARLY THE CONDITION OF THE ESC MEASURES. DEWATERING, AND IN- OR NEAR-WATER WORKS, SHOULD CONCERNS ARISE, THE ENVIRONMENTAL MONITOR WILL CONTACT THE PROPONENT, THE CONSERVATION AUTHORITY, AND ANY OTHER APPROPRIATE PARTIES.
 - EROSION AND SEDIMENT CONTROLS MUST BE MAINTAINED DURING CONSTRUCTION, AND ANY REQUIRED REPAIRS OR REPLACEMENTS MUST BE COMPLETED WITHIN 24 HOURS AFTER THEY HAVE BEEN IDENTIFIED DURING THE MONITORING.
 - EROSION AND SEDIMENT CONTROLS MAY REQUIRE PERIODIC ADJUSTMENTS TO REFLECT CHANGING SITE CONDITIONS. THE CONTRACTOR WILL BE RESPONSIBLE FOR THESE ADJUSTMENTS TO ENSURE PROPER FUNCTION.
 - ANY CHANGES TO THE EROSION AND SEDIMENT CONTROL PLAN BEYOND MINOR ADJUSTMENTS MUST BE APPROVED BY THE CONTRACT ADMINISTRATOR.
 - ADDITIONAL EROSION AND SEDIMENT CONTROL SUPPLIES MUST BE KEPT ON SITE IN ORDER TO FACILITATE IMMEDIATE REPAIRS AND/OR UPGRADES AS NEEDED.
 - ALL TEMPORARY SEDIMENT CONTROLS MUST BE REMOVED AFTER THE CONTRACT ADMINISTRATOR DEEMS THE SITE TO BE STABLE.
 - THE PROJECT PROPONENT OR THEIR REPRESENTATIVE IS ULTIMATELY RESPONSIBLE FOR CONTROLLING SEDIMENT AND EROSION WITHIN THE CONSTRUCTION SITE FOR THE TOTAL PERIOD OF THE CONSTRUCTION.
 - IF EXCESSIVE SILTATION RESULTS FROM THE CONSTRUCTION ACTIVITIES, THE ON-SITE SUPERVISOR/INSPECTOR AND/OR THE LOCAL REGULATORY BODY RESERVE THE RIGHT TO REQUEST ADDITIONAL ESC MEASURES WHICH WOULD BE INSTALLED PRIOR TO FURTHER CONSTRUCTION ACTIVITIES.

- DELETERIOUS SUBSTANCE CONTROL/SPILL MANAGEMENT
- PREVENT THE RELEASE OF SEDIMENT, SEDIMENT-LOADED WATER, RAW CONCRETE, CONCRETE LEACHATE OR ANY OTHER DELETERIOUS SUBSTANCES INTO ANY WATERBODY, RAINE OR STORM SEWER SYSTEM.
 - ENSURE EQUIPMENT AND MACHINERY ARE IN GOOD OPERATING CONDITION (POWER WASHED), FREE OF LEAKS, EXCESS OIL, AND GREASE.
 - NO EQUIPMENT REFUELLING OR SERVICING SHOULD BE UNDERTAKEN WITHIN 30 m OF ANY WATERCOURSE OR SURFACE WATER DRAINAGE.
 - A SPILL CONTAINMENT KIT MUST BE READILY ACCESSIBLE ON SITE IN THE EVENT OF A RELEASE OF A DELETERIOUS SUBSTANCE TO THE ENVIRONMENT. ON-SITE STAFF MUST BE TRAINED IN ITS USE.
 - THE CONTRACT ADMINISTRATOR MUST BE NOTIFIED IMMEDIATELY IN THE EVENT OF A SPILL OF DELETERIOUS SUBSTANCE. ANY SEDIMENT SPILL FROM THE SITE SHOULD BE REPORTED TO MINISTRY OF ENVIRONMENT (SPILL ACTION CENTER) AT 1-800-268-6060.

- WORK AREA ISOLATION
- ALL WORK IN ISOLATED WORK AREAS MUST BE COMPLETED IN THE DRY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
 - CROSSING AN ACTIVE WATERCOURSE OR WETLAND BY EQUIPMENT, VEHICLES, PERSONNEL, ETC. IS NOT PERMITTED UNLESS APPROVED BY THE CONSERVATION AUTHORITY. ALL ACCESS TO WORK SITES SHALL BE FROM EITHER SIDES OF THE WATERCOURSE OR WETLAND.
 - THE UNWATERING DISCHARGE LOCATION MUST BE LOCATED AT LEAST 30 m FROM ANY WATERCOURSE OR WETLAND IN AN AREA WITH DENSE VEGETATIVE GROUND COVER, AND WHERE THE DISCHARGE CAN RETURN TO THE WATERBODY DOWNSTREAM OF THE WORK AREA OVER THE GROUND COVER.
 - FISH MUST BE REMOVED FROM THE WORK AREA ONCE ISOLATED. FISH SALVAGE MUST BE COMPLETED BY A QUALIFIED TECHNICIAN WITH A LICENSE FROM THE ONTARIO MINISTRY OF NATURAL RESOURCES AND FORESTRY.

1.	24/03/15	LD	FIRST CONCEPTUAL DESIGN SUBMISSION
	DATE	BY	REVISIONS
DESIGNED BY:	LD		CHECKED BY: PV
DRAWN BY:	AS / SG		DATE: APRIL 2024
		<div><div>NOT FOR CONSTRUCTION SCALED FOR PLOT ON 'ARCH D'</div><div><div>GEO</div><div>MORPHIX™ 36 Main St N., P.O. Box 205 Campbellville, Ontario L0P 1B0 T: 416.920.0926 www.geomorphix.com</div></div></div>	
		24/03/15	

BLOCK 1 BSS FRUITLAND-WINONA BLOCK 1 OWNERS GROUP, HAMILTON	
WATERCOURSE 5 CONCEPTUAL CHANNEL DESIGN PLANFORM AND PROFILE	
PROJECT No.: 21043	DRAWING No.: GEO-2
SCALE: AS NOTED	SHEET 2 OF 5



- GENERAL NOTES
- THE ACCOMPANYING CHANNEL REALIGNMENT TECHNICAL DESIGN BRIEF PREPARED BY GEO MORPHIX LTD. (2023) PROVIDES ADDITIONAL DESIGN DETAILS AND DIRECTION FOR IMPLEMENTATION AND IS TO BE REVIEWED IN CONJUNCTION WITH THIS DRAWING SET.
 - ALL CONTRACT DRAWINGS, SPECIFICATIONS AND APPLICABLE PERMITS MUST BE KEPT ON SITE DURING CONSTRUCTION FOR REFERENCE.
 - THE CONTRACTOR MUST NOTIFY THE DESIGNER AND CONTRACT ADMINISTRATOR OF THE INTENT TO COMMENCE WORK AT LEAST 48 HOURS IN ADVANCE.
 - THE CONTRACTOR IS RESPONSIBLE FOR ALL UTILITY LOCATES.
 - LAYOUT MUST BE REVIEWED AND APPROVED BY THE DESIGNER / DESIGNER REPRESENTATIVE, DESIGNATED ENGINEER, AND THE CONTRACT ADMINISTRATOR.
 - CONSTRUCTION OBSERVATION IS TO BE PERFORMED BY A CERTIFIED FLUVIAL GEOMORPHOLOGIST OR EXPERIENCED ENVIRONMENTAL INSPECTOR UNDER DIRECTION FROM THE DESIGNER.
 - ON-SITE SUPPORT FROM PROJECT ENGINEER (E.G. GEOTECHNICAL, HYDROGEOLOGICAL, AND/OR WATER RESOURCES ENGINEER) REQUIRED TO ASSESS AND ENSURE FAVOURABLE SURFICIAL AND SUBSURFACE CONDITIONS TO SUPPORT CHANNEL REALIGNMENT CONSTRUCTION.
 - BE ADVISED THAT THE LOCAL REGULATORY BODY MAY, AT ANY TIME, WITHDRAW THIS PERMISSION, IF, IN THE OPINION OF THE AUTHORITY, THE CONDITIONS OF THE PERMIT ARE NOT BEING COMPLIED WITH. THIS APPROVAL DOES NOT EXEMPT THE PROPERTY OWNER/APPLICANT/AGENT FROM THE PROVISIONS OF ANY OTHER FEDERAL, PROVINCIAL OR MUNICIPAL STATUTES, REGULATIONS OR BY-LAWS, OR ANY RIGHTS UNDER COMMON LAW.

- TIMING OF WORKS
- WORKS SHALL BE COMPLETED DURING THE DESIGNATED IN-WATER WORKS WINDOW SET OUT BY MNRF/DO.
 - TREE CLEARING IS TO BE COMPLETED OUTSIDE THE BIRD NESTING SEASON (APRIL 1ST TO AUGUST 1ST) TO COMPLY WITH THE FEDERAL MIGRATORY BIRDS CONVENTION ACT. ANY TREES THAT REQUIRE REMOVAL OUTSIDE OF THIS TIMING WINDOW MUST FIRST BE INSPECTED BY A QUALIFIED BIOLOGIST TO DETERMINE THE PRESENCE OF NESTING BIRDS.
 - THE WEATHER FORECAST SHOULD BE CONTINUALLY MONITORED TO ENSURE THAT WORKS ARE UNDERTAKEN ONLY DURING FAVOURABLE WEATHER CONDITIONS.
 - COMPLETE THE WORKS WITH MINIMAL AVOIDABLE INTERRUPTIONS ONCE THEY COMMENCE.


- SITE AND MATERIAL MANAGEMENT
- ALL CONSTRUCTION EQUIPMENT AND MATERIALS (IMPORTED OR EXCAVATED) MUST BE STORED AT LEAST 30 m AWAY FROM ANY WATERBODY IN A STABLE AREA ABOVE THE ACTIVE FLOODPLAIN, OR IN A DESIGNATED STAGING/STORAGE AREA.
 - IN THE EVENT OF AN UNEXPECTED STORM, ALL UNFIXED ITEMS THAT HAVE THE POTENTIAL TO CAUSE A SPILL OR AN OBSTRUCTION TO FLOW MUST BE MOVED A STABLE AREA ABOVE ACTIVE FLOODPLAIN.
 - STOCKPILES MUST BE LOCATED OUTSIDE THE ISOLATED WORK AREAS.
 - STABILIZE, TEMPORARILY OR PERMANENTLY, ANY DISTURBED AREAS AS WORK PROGRESSES, OR SOON AS CONDITIONS ALLOW.
 - MINIMIZE THE AREA OF DISTURBANCE TO THE EXTENT POSSIBLE. ALL DISTURBED GROUND LEFT INACTIVE FOR MORE THAN 30 DAYS SHALL BE STABILIZED USING APPROPRIATE EROSION CONTROL MEASURES AND AN APPROPRIATE SEED MIX AS NOTED WITHIN THE FINAL APPROVED RESTORATION PLAN.
 - ALL VEGETATION, ADJACENT TO THE WORK AREA, MUST BE PROTECTED AND DELINEATED WITH CONSTRUCTION FENCING OR TREE PROTECTION BARRIERS.
 - ALL GRADES IN THE AREA REGULATED BY THE CONSERVATION AUTHORITY MUST BE MAINTAINED OR MATCHED, UNLESS OTHERWISE AUTHORIZED IN THE APPLICABLE PERMIT.
 - AN AFTER-HOURS CONTACT NUMBER IS TO BE VISIBLY POSTED ON-SITE FOR EMERGENCIES. ALL THE PLANS SHOULD HAVE NAME AND CONTACT INFO OF THE PERSON RESPONSIBLE FOR ESC MEASURES.

- EROSION AND SEDIMENT CONTROL
- ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSTALLED PRIOR TO START OF WORKS. FOLLOWING INSTALLATION OF THE PROPOSED ESC MEASURES, A QUALIFIED AGENT OF THE PROPONENT (E.G. CAN-CISEC CERTIFIED MONITOR) WILL CONDUCT REGULAR SITE VISITS TO MONITOR ALL WORKS, PARTICULARLY THE CONDITION OF THE ESC MEASURES. DEWATERING, AND IN- OR NEAR-WATER WORKS, SHOULD CONCERNS ARISE, THE ENVIRONMENTAL MONITOR WILL CONTACT THE PROPONENT, THE CONSERVATION AUTHORITY, AND ANY OTHER APPROPRIATE PARTIES.
 - EROSION AND SEDIMENT CONTROLS MUST BE MAINTAINED DURING CONSTRUCTION, AND ANY REQUIRED REPAIRS OR REPLACEMENTS MUST BE COMPLETED WITHIN 24 HOURS AFTER THEY HAVE BEEN IDENTIFIED DURING THE MONITORING.
 - EROSION AND SEDIMENT CONTROLS MAY REQUIRE PERIODIC ADJUSTMENTS TO REFLECT CHANGING SITE CONDITIONS. THE CONTRACTOR WILL BE RESPONSIBLE FOR THESE ADJUSTMENTS TO ENSURE PROPER FUNCTION.
 - ANY CHANGES TO THE EROSION AND SEDIMENT CONTROL PLAN BEYOND MINOR ADJUSTMENTS MUST BE APPROVED BY THE CONTRACT ADMINISTRATOR.
 - ADDITIONAL EROSION AND SEDIMENT CONTROL SUPPLIES MUST BE KEPT ON SITE IN ORDER TO FACILITATE IMMEDIATE REPAIRS AND/OR UPGRADES AS NEEDED.
 - ALL TEMPORARY SEDIMENT CONTROLS MUST BE REMOVED AFTER THE CONTRACT ADMINISTRATOR DEEMS THE SITE TO BE STABLE.
 - THE PROJECT PROPONENT OR THEIR REPRESENTATIVE IS ULTIMATELY RESPONSIBLE FOR CONTROLLING SEDIMENT AND EROSION WITHIN THE CONSTRUCTION SITE FOR THE TOTAL PERIOD OF THE CONSTRUCTION.
 - IF EXCESSIVE SILTATION RESULTS FROM THE CONSTRUCTION ACTIVITIES, THE ON-SITE SUPERVISOR/INSPECTOR AND/OR THE LOCAL REGULATORY BODY RESERVE THE RIGHT TO REQUEST ADDITIONAL ESC MEASURES WHICH WOULD BE INSTALLED PRIOR TO FURTHER CONSTRUCTION ACTIVITIES.

- DELETERIOUS SUBSTANCE CONTROL/SPILL MANAGEMENT
- PREVENT THE RELEASE OF SEDIMENT, SEDIMENT-LOADED WATER, RAW CONCRETE, CONCRETE LEACHATE OR ANY OTHER DELETERIOUS SUBSTANCES INTO ANY WATERBODY, RAVINE OR STORM SEWER SYSTEM.
 - ENSURE EQUIPMENT AND MACHINERY ARE IN GOOD OPERATING CONDITION (POWER WASHED), FREE OF LEAKS, EXCESS OIL, AND GREASE.
 - NO EQUIPMENT REFUELLING OR SERVICING SHOULD BE UNDERTAKEN WITHIN 30 m OF ANY WATERCOURSE OR SURFACE WATER DRAINAGE.
 - A SPILL CONTAINMENT KIT MUST BE READILY ACCESSIBLE ON SITE IN THE EVENT OF A RELEASE OF A DELETERIOUS SUBSTANCE TO THE ENVIRONMENT. ON-SITE STAFF MUST BE TRAINED IN ITS USE.
 - THE CONTRACT ADMINISTRATOR MUST BE NOTIFIED IMMEDIATELY IN THE EVENT OF A SPILL OF DELETERIOUS SUBSTANCE. ANY SEDIMENT SPILL FROM THE SITE SHOULD BE REPORTED TO MINISTRY OF ENVIRONMENT (SPILL ACTION CENTER) AT 1-800-268-6060.

- WORK AREA ISOLATION
- ALL WORK IN ISOLATED WORK AREAS MUST BE COMPLETED IN THE DRY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
 - CROSSING AN ACTIVE WATERCOURSE OR WETLAND BY EQUIPMENT, VEHICLES, PERSONNEL, ETC. IS NOT PERMITTED UNLESS APPROVED BY THE CONSERVATION AUTHORITY. ALL ACCESS TO WORK SITES SHALL BE FROM EITHER SIDES OF THE WATERCOURSE OR WETLAND.
 - THE UNWATERING DISCHARGE LOCATION MUST BE LOCATED AT LEAST 30 m FROM ANY WATERCOURSE OR WETLAND IN AN AREA WITH DENSE VEGETATIVE GROUND COVER, AND WHERE THE DISCHARGE CAN RETURN TO THE WATERBODY DOWNSTREAM OF THE WORK AREA OVER THE GROUND COVER.
 - FISH MUST BE REMOVED FROM THE WORK AREA ONCE ISOLATED. FISH SALVAGE MUST BE COMPLETED BY A QUALIFIED TECHNICIAN WITH A LICENSE FROM THE ONTARIO MINISTRY OF NATURAL RESOURCES AND FORESTRY.


1.	24/03/15	LD	FIRST CONCEPTUAL DESIGN SUBMISSION
	DATE	BY	REVISIONS
DESIGNED BY:	LD		CHECKED BY: PV
DRAWN BY:	AS / SG		DATE: APRIL 2024
<div><div>NOT FOR CONSTRUCTION SCALED FOR PLOT ON 'ARCH D'</div><div><div>GEO</div><div>MORPHIX™ 36 Main St N., P.O. Box 205 Campbellville, Ontario L0P 1B0 T: 416.920.0926 www.geomorphix.com</div></div></div>			
24/03/15			
BLOCK 1 BSS FRUITLAND-WINONA BLOCK 1 OWNERS GROUP, HAMILTON			
WATERCOURSE 5 CONCEPTUAL CHANNEL DESIGN PLANFORM AND PROFILE			
PROJECT No.: 21043		DRAWING No.: GEO-3	
SCALE: AS NOTED		SHEET 3 OF 5	




CHANNEL SUBSTRATE NOTES

- SUBSTRATES TO BE COMPACTED TO 90% SPD TO PREVENT PIPING/FLOW-THROUGH.
- FINE NATIVE MATERIAL TO BE ADDED TO SUBSTRATE MIX TO FILL INTERSTITIAL VOIDS, AS REQUIRED.
- GRANULAR 'B' TO BE SOURCED FROM PIT-RUN MATERIAL AND ROUNDED IN NATURE. NO CRUSHED ROCK, LIMESTONE OR POST-CONSTRUCTION MATERIALS ARE TO BE USED WITHIN THE CHANNEL. MATERIAL TO BE REVIEWED BY THE DESIGNER OR REPRESENTATIVE PRIOR TO INSTALLATION.

TYPICAL RIFFLE




CHANNEL CROSS SECTIONS
N.T.S.



OVERWINTER POOL TYPICAL SECTION
N.T.S.


NOTE: SEED IS TO BE PLACED PRIOR TO INSTALLATION OF EROSION CONTROL BLANKET. REFER TO LANDSCAPE DRAWINGS FOR SEED MIX SPECIFICATIONS.



NOTES

- LIVE BRANCHES TO CONSIST OF WILLOW AND DOGWOOD SPECIES, APPROXIMATELY 1 m IN LENGTH AND 50 mm - 100 mm IN WIDTH.
- SOURCE MATERIAL FOR BRUSH MATTRESS SHOULD BE CONFIRMED BY THE DESIGNER OR REPRESENTATIVE.
- BRANCHES TO BE KEPT IN MOIST AND COLD UNTIL INSTALLATION.
- BRUSH MATTRESS TO BE INSTALLED WHILE BRANCHES ARE DORMANT.
- BRANCHES TO BE PLACED ON SLOPE WITH BUTT END TOWARDS VALLEY FLOOR AND PUSHED INTO SOIL.
- BRANCHES MUST BE FLEXIBLE ENOUGH TO CONFORM TO THE SLOPE SURFACE IRREGULARITIES.
- POUND DEAD STAKES TO HALF THEIR LENGTH INTO SOIL BETWEEN BRANCHES. TIE COIR TWINE AROUND DEAD STAKES AND TIGHTLY OVER BRANCHES. USE A CLOVE HITCH TO SECURE STAKES. POUND STAKES INTO SLOPE TO COMPRESS BRANCHES AGAINST GROUND.
- TAMP LIVE STAKES BETWEEN DEAD STAKES.
- FILL VOIDS BETWEEN BRANCHES OF THE BRUSH MATTRESS WITH SOIL TO PROMOTE ROOTING.


BRUSH MATTRESS
N.T.S.



NOTES

- HEIGHT OF TERRESTRIAL MOUND SHALL BE 1000 mm TO 2000 mm.
- PLACEMENT OF VEGETATED TERRESTRIAL MOUND TO BE AS PER PLAN, IN DRY AREAS ONLY.
- CONSTRUCTION OF MOUND TO BE COMPLETED IN CONJUNCTION WITH SITE GRADING ACTIVITIES AS TERRESTRIAL MOUNDS TO BE GRADED TO MATCH EXISTING GROUND AND/OR TIE INTO EXISTING SLOPES.
- TERRESTRIAL MOUND TO BE SLIGHTLY CONCAVE/DIMPLED ON TOP.
- SEED MIX TO BE COMPRISED OF RIPARIAN / UPLAND SPECIES AS PER PLANTING PLAN.


TERRESTRIAL MOUND
N.T.S.



NOTES

- LARGEST AND HEAVIEST LOG MATERIAL SHOULD BE PLACED ON THE BASE OF THE BRUSH PILE. THE SMALLEST BRUSH MATERIAL SHOULD BE PLACED AT THE TOP.
- LOGS SHOULD BE FORMED INTO A PALLET SHAPE.
- HEIGHT OF BRUSH PILE IS NOT TO EXCEED 1.0 M.
- A MIX OF HARDWOOD AND SOFTWOOD SHOULD BE USED.
- PLANT WITH NATIVE FRUIT BEARING VINES.

PALLET TYPE WOOD PILE
N.T.S.



GENERAL NOTES

- THE ACCOMPANYING CHANNEL REALIGNMENT TECHNICAL DESIGN BRIEF PREPARED BY GEO MORPHIX LTD. (2023) PROVIDES ADDITIONAL DESIGN DETAILS AND DIRECTION FOR IMPLEMENTATION AND IS TO BE REVIEWED IN CONJUNCTION WITH THIS DRAWING SET.
- ALL CONTRACT DRAWINGS, SPECIFICATIONS AND APPLICABLE PERMITS MUST BE KEPT ON SITE DURING CONSTRUCTION FOR REFERENCE.
- THE CONTRACTOR MUST NOTIFY THE DESIGNER AND CONTRACT ADMINISTRATOR OF THE INTENT TO COMMENCE WORK AT LEAST 48 HOURS IN ADVANCE.
- THE CONTRACTOR IS RESPONSIBLE FOR ALL UTILITY LOCATES.
- LAYOUT MUST BE REVIEWED AND APPROVED BY THE DESIGNER / DESIGNER REPRESENTATIVE, DESIGNATED ENGINEER, AND THE CONTRACT ADMINISTRATOR.
- CONSTRUCTION OBSERVATION IS TO BE PERFORMED BY A CERTIFIED FLUVIAL GEOMORPHOLOGIST OR EXPERIENCED ENVIRONMENTAL INSPECTOR UNDER DIRECTION FROM THE DESIGNER.
- ON-SITE SUPPORT FROM PROJECT ENGINEER (E.G. GEOTECHNICAL, FLUVIAL GEOMORPHOLOGIST, AND/OR WATER RESOURCES ENGINEER) REQUIRED TO ASSESS AND ENSURE FAVOURABLE SURFICIAL AND SUBSURFACE CONDITIONS TO SUPPORT CHANNEL REALIGNMENT CONSTRUCTION.
- BE ADVISED THAT THE LOCAL REGULATORY BODY MAY, AT ANY TIME, WITHDRAW THIS PERMISSION, IF, IN THE OPINION OF THE AUTHORITY, THE CONDITIONS OF THE PERMIT ARE NOT BEING COMPLIED WITH. THIS APPROVAL DOES NOT EXEMPT THE PROPERTY OWNER/APPLICANT/AGENT FROM THE PROVISIONS OF ANY OTHER FEDERAL, PROVINCIAL OR MUNICIPAL STATUTES, REGULATIONS OR BY-LAWS, OR ANY RIGHTS UNDER COMMON LAW.

TIMING OF WORKS

- WORKS SHALL BE COMPLETED DURING THE DESIGNATED IN-WATER WORKS WINDOW SET OUT BY MNRF/DO.
- TREE CLEARING IS TO BE COMPLETED OUTSIDE THE BIRD NESTING SEASON (APRIL 1ST TO AUGUST 1ST) TO COMPLY WITH THE FEDERAL MIGRATORY BIRDS CONVENTION. ANY TREES THAT REQUIRE REMOVAL OUTSIDE OF THIS TIMING WINDOW MUST FIRST BE INSPECTED BY A QUALIFIED BIOLOGIST TO DETERMINE THE PRESENCE OF NESTING BIRDS.
- THE WEATHER FORECAST SHOULD BE CONTINUALLY MONITORED TO ENSURE THAT WORKS ARE UNDERTAKEN ONLY DURING FAVOURABLE WEATHER CONDITIONS.
- COMPLETE THE WORKS WITH MINIMAL AVOIDABLE INTERRUPTIONS ONCE THEY COMMENCE.

SITE AND MATERIAL MANAGEMENT

- ALL CONSTRUCTION EQUIPMENT AND MATERIALS (IMPORTED OR EXCAVATED) MUST BE STORED AT LEAST 30 m AWAY FROM ANY WATERBODY (A STABLE AREA ABOVE THE ACTIVE FLOODPLAIN, OR IN A DESIGNATED STAGING/STORAGE AREA).
- IN THE EVENT OF AN UNEXPECTED STORM, ALL UNFIXED ITEMS THAT HAVE THE POTENTIAL TO CAUSE A SPILL OR AN OBSTRUCTION TO FLOW MUST BE MOVED A STABLE AREA ABOVE ACTIVE FLOODPLAIN.
- STOCKPILES MUST BE LOCATED OUTSIDE THE ISOLATED WORK AREAS.
- STABILIZE, TEMPORARILY OR PERMANENTLY, ANY DISTURBED AREAS AS WORK PROGRESSES, OR SOON AS CONDITIONS ALLOW.
- MINIMIZE THE AREA OF DISTURBANCE TO THE EXTENT POSSIBLE. ALL DISTURBED GROUND LEFT INACTIVE FOR MORE THAN 30 DAYS SHALL BE STABILIZED USING APPROPRIATE EROSION CONTROL MEASURES AND AN APPROPRIATE SEED MIX AS NOTED WITHIN THE FINAL APPROVED RESTORATION PLAN.
- ALL VEGETATION, ADJACENT TO THE WORK AREA, MUST BE PROTECTED AND DELINEATED WITH CONSTRUCTION FENCING OR TREE PROTECTION BARRIERS.
- ALL GRADES IN THE AREA REGULATED BY THE CONSERVATION AUTHORITY MUST BE MAINTAINED OR MATCHED, UNLESS OTHERWISE AUTHORIZED IN THE APPLICABLE PERMIT.
- AN AFTER-HOURS CONTACT NUMBER IS TO BE VISIBLY POSTED ON-SITE FOR EMERGENCIES. ALL PLANS SHOULD HAVE NAME AND CONTACT INFO OF THE PERSON RESPONSIBLE FOR ESC MEASURES.

EROSION AND SEDIMENT CONTROL


- ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSTALLED PRIOR TO START OF WORKS. FOLLOWING INSTALLATION OF THE PROPOSED ESC MEASURES, A QUALIFIED AGENT OF THE PROPONENT (E.G. CAN-CISEC CERTIFIED MONITOR) WILL CONDUCT REGULAR SITE VISITS TO MONITOR ALL WORKS, PARTICULARLY THE CONDITION OF THE ESC MEASURES. DEWATERING, AND IN-OR NEAR-WATER WORKS, SHOULD CONCERNS ARISE, THE ENVIRONMENTAL MONITOR WILL CONTACT THE PROPONENT, THE CONSERVATION AUTHORITY, AND ANY OTHER APPROPRIATE PARTIES.
- EROSION AND SEDIMENT CONTROLS MUST BE MAINTAINED DURING CONSTRUCTION, AND ANY REQUIRED REPAIRS OR REPLACEMENTS MUST BE COMPLETED WITHIN 24 HOURS AFTER THEY HAVE BEEN IDENTIFIED DURING THE MONITORING.
- EROSION AND SEDIMENT CONTROLS MAY REQUIRE PERIODIC ADJUSTMENTS TO REFLECT CHANGING SITE CONDITIONS. THE CONTRACTOR WILL BE RESPONSIBLE FOR THESE ADJUSTMENTS TO ENSURE PROPER FUNCTION.
- ANY CHANGES TO THE EROSION AND SEDIMENT CONTROL PLAN BEYOND MINOR ADJUSTMENTS MUST BE APPROVED BY THE CONTRACT ADMINISTRATOR.
- ADDITIONAL EROSION AND SEDIMENT CONTROL SUPPLIES MUST BE KEPT ON SITE IN ORDER TO FACILITATE IMMEDIATE REPAIRS AND/OR UPGRADES AS NEEDED.
- ALL TEMPORARY SEDIMENT CONTROLS MUST BE REMOVED AFTER THE CONTRACT ADMINISTRATOR DEEMS THE SITE TO BE STABLE.
- THE PROJECT PROPONENT OR THEIR REPRESENTATIVE IS ULTIMATELY RESPONSIBLE FOR CONTROLLING SEDIMENT AND EROSION WITHIN THE CONSTRUCTION SITE FOR THE TOTAL PERIOD OF THE CONSTRUCTION.
- IF EXCESSIVE SILTATION RESULTS FROM THE CONSTRUCTION ACTIVITIES, THE ON-SITE SUPERVISOR/INSPECTOR AND/OR THE LOCAL REGULATORY BODY RESERVE THE RIGHT TO REQUEST ADDITIONAL ESC MEASURES WHICH WOULD BE INSTALLED PRIOR TO FURTHER CONSTRUCTION ACTIVITIES.

DELETERIOUS SUBSTANCE CONTROL/SPILL MANAGEMENT

- PREVENT THE RELEASE OF SEDIMENT, SEDIMENT-LOADED WATER, RAW CONCRETE, CONCRETE LEACHATE OR ANY OTHER DELETERIOUS SUBSTANCES INTO ANY WATERBODY, RAVINE OR STORM SEWER SYSTEM.
- ENSURE EQUIPMENT AND MACHINERY ARE IN GOOD OPERATING CONDITION (POWER WASHED), FREE OF LEAKS, EXCESS OIL AND GREASE.
- NO EQUIPMENT REFUELLING OR SERVICING SHOULD BE UNDERTAKEN WITHIN 30 m OF ANY WATERCOURSE OR SURFACE WATER DRAINAGE.
- A SPILL CONTAINMENT KIT MUST BE READILY ACCESSIBLE ON SITE IN THE EVENT OF A RELEASE OF A DELETERIOUS SUBSTANCE TO THE ENVIRONMENT. ON-SITE STAFF MUST BE TRAINED IN ITS USE.
- THE CONTRACT ADMINISTRATOR MUST BE NOTIFIED IMMEDIATELY IN THE EVENT OF A SPILL OF DELETERIOUS SUBSTANCE. ANY SEDIMENT SPILL FROM THE SITE SHOULD BE REPORTED TO MINISTRY OF ENVIRONMENT (SPILL ACTION CENTER) AT 1-800-268-6060.

WORK AREA ISOLATION


- ALL WORK IN ISOLATED WORK AREAS MUST BE COMPLETED IN THE DRY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
- CROSSING AN ACTIVE WATERCOURSE OR WETLAND BY EQUIPMENT, VEHICLES, PERSONNEL, ETC. IS NOT PERMITTED UNLESS APPROVED BY THE CONSERVATION AUTHORITY. ALL ACCESS TO WORK SITES SHALL BE FROM EITHER SIDES OF THE WATERCOURSE OR WETLAND.
- THE UNWATERING DISCHARGE LOCATION MUST BE LOCATED AT LEAST 30 m FROM ANY WATERCOURSE OR WETLAND IN AN AREA WITH DENSE VEGETATIVE GROUND COVER, AND WHERE THE DISCHARGE CAN RETURN TO THE WATERBODY DOWNSTREAM OF THE WORK AREA OVER THE GROUND COVER.
- FISH MUST BE REMOVED FROM THE WORK AREA ONCE ISOLATED. FISH SALVAGE MUST BE COMPLETED BY A QUALIFIED TECHNICIAN WITH A LICENSE FROM THE ONTARIO MINISTRY OF NATURAL RESOURCES AND FORESTRY.

1.	24/03/15	LD	FIRST CONCEPTUAL DESIGN SUBMISSION
	DATE	BY	REVISIONS
DESIGNED BY: LD		CHECKED BY: PV	
DRAWN BY: AS / SG		DATE: APRIL 2024	
<div>NOT FOR CONSTRUCTION SCALED FOR PLOT ON 'ARCH D'</div>		<div><p>M O R P H I X™ 36 Main St N., P.O. Box 205 Campbellville, Ontario L0P 1B0 T: 416.920.0926 www.geomorphix.com</p></div>	
24/03/15			

BLOCK 1 BSS
FRUITLAND-WINONA BLOCK 1 OWNERS
GROUP, HAMILTON

WATERCOURSE 5
CONCEPTUAL CHANNEL DESIGN
DETAILS


PROJECT No.: 21043	DRAWING No.: DET-1
SCALE: AS NOTED	SHEET 4 OF 5



NOTE: SEED IS TO BE PLACED PRIOR TO INSTALLATION OF EROSION CONTROL BLANKET. REFER TO LANDSCAPE DRAWINGS FOR SEED MIX SPECIFICATIONS.

WETLAND CROSS SECTION
N.T.S.


- SUBSTRATE NOTES**
1. SUBSTRATES TO BE COMPACTED TO 90% SPD TO PREVENT PIPING/FLOW-THROUGH.
 2. FINE NATIVE MATERIAL TO BE ADDED TO SUBSTRATE MIX TO FILL INTERSTITIAL VOIDS, AS REQUIRED.
 3. GRANULAR 'B' TO BE SOURCED FROM PIT-RUN MATERIAL AND ROUNDED IN NATURE. NO CRUSHED ROCK, LIMESTONE OR POST-CONSTRUCTION MATERIALS ARE TO BE USED WITHIN THE CHANNEL. MATERIAL TO BE REVIEWED BY THE DESIGNER OR REPRESENTATIVE PRIOR TO INSTALLATION.



WETLAND SUBSTRATE NOTES

1. SUBSTRATES TO BE COMPACTED TO 90% SPD TO PREVENT PIPING/FLOW-THROUGH.
2. FINE NATIVE MATERIAL TO BE ADDED TO SUBSTRATE MIX TO FILL INTERSTITIAL VOIDS, AS REQUIRED.
3. GRANULAR 'B' TO BE SOURCED FROM PIT-RUN MATERIAL AND ROUNDED IN NATURE. NO CRUSHED ROCK, LIMESTONE OR POST-CONSTRUCTION MATERIALS ARE TO BE USED WITHIN THE CHANNEL. MATERIAL TO BE REVIEWED BY THE DESIGNER OR REPRESENTATIVE PRIOR TO INSTALLATION.

ONLINE WETLAND CROSS SECTION
N.T.S.



SPECIES AND QUANTITIES

COMMON NAME	SCIENTIFIC NAME	SIZE
RED OSIER DOGWOOD	<i>Cornus stolonifera</i>	1 m
PUSSY WILLOW	<i>Salix discolor</i>	1 m
SANDBAR WILLOW	<i>Salix exigua</i>	1 m


NOTES

1. QUANTITY TO BE DETERMINED BASED ON AREA OF DISTURBANCE TO BE RESTORED
2. LIVE STAKES SHOULD BE FROM AT MINIMUM 2-YEAR OLD STOCK
3. LIVE STAKES ARE TO BE INSTALLED AT A DENSITY OF 3 STAKES PER SQUARE METRE.
4. LIVE STAKES SHOULD BE PRE-SOAKED (SUBMERGED IN WATER) FOR AT LEAST 24 HOURS AFTER HARVESTING AND IMMEDIATELY BEFORE INSTALLATION.
5. LIVE STAKES SHOULD NOT BE STORED FOR A PERIOD LONGER THAN 2 DAYS, UNLESS THEY ARE BEING SOAKED.
6. THE CONTRACTOR SHALL PROTECT PLANT MATERIALS FROM DRYING FROM THE TIME OF HARVEST UNTIL INSTALLED.
7. LIVE STAKES ARE TO BE A MINIMUM OF 25 mm IN DIAMETER AND CUT TO A LENGTH OF 1000 mm.
8. CUT ANGLE AT THE BOTTOM OF THE STAKE AND FLAT ON THE TOP.
9. TRIM ALL SIDE BRANCHES WHILE TAKING CARE NOT TO DAMAGE THE BARK.
10. INSTALL STAKES WITH BUDS POINTING UPWARDS AND THICKER STEM IN THE BED.
11. LIVE STAKES SHOULD BE INSTALLED USING A LARGE RUBBER Mallet.
12. 80% OF THE STAKE IS TO BE BELOW SURFACE.
13. TAMP THE LIVE STAKE INTO THE GROUND AT RIGHT ANGLE TO THE SURFACE.
14. IN COMPACT SOIL A PILOT HOLE SHOULD BE USED TO LIMIT DAMAGE TO THE STAKES.
15. IF USING A PILOT HOLE REPACK SOIL AROUND THE LIVE STAKE.
16. LIVE STAKES SHOULD STAND FIRM FROM THE SOIL FOLLOWING INSTALLATION.
17. ALL STAKES NOT PLANTED TO THE SPECIFICATIONS ABOVE WILL BE REPLACED AT THE CONTRACTOR'S EXPENSE.

LIVE STAKE
N.T.S.

EROSION CONTROL BLANKET SPECIFICATIONS


1. A BIODEGRADABLE EROSION CONTROL BLANKET (ECB) SHALL BE INSTALLED ON ALL DISTURBED NATURAL SURFACES FOLLOWING THE PLACEMENT OF TOPSOIL AND APPLICATION OF THE NATIVE SEED MIX.
2. THE ECB MUST BE CONSTRUCTED OF 100% WOVEN COCONUT FIBRE (E.G., COIR) OR STRAW MAT WITHIN A GEOJUTE NETTING (TOP AND BOTTOM) WITH BIODEGRADABLE THREAD. NON-BIODEGRADABLE MATERIAL INCLUDING POLYPROPYLENE OR PLASTICS WITH A BIODEGRADABLE RATING ARE NOT ACCEPTABLE. THE MINIMUM WEIGHT OF THE ECB MUST BE 400 g/m² (12 oz./yd²).
3. TO INSTALL, THE ECB MUST BE UNROLLED DOWNSLOPE OR IN DIRECTION OF WATER FLOW. ADJACENT ECBs SHOULD OVERLAP A MINIMUM OF 150 mm ALONG THE EDGES. AT THE END OF EACH ROLL, FOLD BACK 100 mm TO 200 mm OF THE ECB. OVERLAP THIS 100 mm TO 200 mm OVER THE START OF THE NEXT ROLL. SECURE THE TWO LAYERS TO THE GROUND SECURELY.
4. BIODEGRADABLE OR TAPERED WOODEN STAKES SHALL BE USED TO SECURE THE BLANKET. STAKES SHALL BE INSTALLED AT THE SPACING RECOMMENDED BY THE ECB MANUFACTURER TO PREVENT SURFACE RUNOFF FROM ERODING THE UNDERLYING SOIL.



NOTES

1. CONSTRUCT WITH CONIFER TRUNKS WITH TWO OR MORE NATURAL BRANCHES.
2. AT LEAST 75% OF THE BARK SHOULD BE INTACT.
3. AUGER HOLE TO A DEPTH OF ~1.0 m INSTALL TRUNK AND TAMP IN SAND AROUND BASE.
4. ~1.0 m OF TRUNK IS TO BE BURIED.
5. PLACE 0.50 m - 0.60 m STONE AROUND BASE FOR ADDITIONAL SUPPORT.
6. IF ROOT WAD IS USED PLACE ROOT AT TOP.
7. LOGS SHOULD BE SOURCED ON SITE (WHERE POSSIBLE).
8. AT LEAST 4 RAPTOR POLES ARE TO BE 5 m IN HEIGHT.


RAPTOR POLE
N.T.S.



NOTES

1. 50 mm - 200 mm STONE MIX WITH SOME ANGULAR STONES.
2. THE STONE MIX SHOULD PROVIDE A VARIETY OF INTERSTITIAL SPACES.
3. PILES ARE AT LEAST 1500 mm IN DIAMETER AND ~1000 mm HIGH.
4. PARTIALLY BURY PILES 300 - 400 mm TO AVOID ROCKFALL.


ROCK PILE
N.T.S.



NOTES

1. ANCHOR AND SUPPORT BASKING LOGS WITH 75 mm - 200 mm STONE MIX.
2. FIRMLY COMPACT STONE MIX TO PREVENT THROUGH FLOW.
3. BURY 1/3 OF LOG INTO SOIL.
4. LENGTH OF BASKING LOGS ARE TO BE INSTALLED 1000 - 1500 mm INTO WET AREA.
5. BASKING LOGS TO BE A MINIMUM 500 mm IN DIAMETER AND 2000 - 2500 mm IN LENGTH.
6. BASKING LOGS SHOULD BE ANGLED TO PROMOTE TURTLE BASKING.
7. BASKING LOGS SHOULD BE A MIXTURE OF SUITABLE HARDWOOD AND SOFTWOOD SPECIES.
8. BASKING LOGS SHOULD BE DOUBLED UP IN SPECIFIED LOCATIONS

BASKING LOG
N.T.S.



GENERAL NOTES

1. THE ACCOMPANYING CHANNEL REALIGNMENT TECHNICAL DESIGN BRIEF PREPARED BY GEO MORPHIX LTD. (2023) PROVIDES ADDITIONAL DESIGN DETAILS AND DIRECTION FOR IMPLEMENTATION AND IS TO BE REVIEWED IN CONJUNCTION WITH THIS DRAWING SET.
2. ALL CONTRACT DRAWINGS, SPECIFICATIONS AND APPLICABLE PERMITS MUST BE KEPT ON SITE DURING CONSTRUCTION FOR REFERENCE.
3. THE CONTRACTOR MUST NOTIFY THE DESIGNER AND CONTRACT ADMINISTRATOR OF THE INTENT TO COMMENCE WORK AT LEAST 48 HOURS IN ADVANCE.
4. THE CONTRACTOR IS RESPONSIBLE FOR ALL UTILITY LOCATES.
5. LAYOUT MUST BE REVIEWED AND APPROVED BY THE DESIGNER / DESIGNER REPRESENTATIVE, DESIGNATED ENGINEER, AND THE CONTRACT ADMINISTRATOR.
6. CONSTRUCTION OBSERVATION IS TO BE PERFORMED BY A CERTIFIED FLUVIAL GEOMORPHOLOGIST OR EXPERIENCED ENVIRONMENTAL INSPECTOR UNDER DIRECTION FROM THE DESIGNER.
7. ON-SITE SUPPORT FROM PROJECT ENGINEER (E.G., GEOTECHNICAL, HYDROLOGICAL, AND/OR WATER RESOURCES ENGINEER) REQUIRED TO ASSESS AND ENSURE FAVOURABLE SURFICIAL AND SUBSURFACE CONDITIONS TO SUPPORT CHANNEL REALIGNMENT CONSTRUCTION.
8. BE ADVISED THAT THE LOCAL REGULATORY BODY MAY, AT ANY TIME, WITHDRAW THIS PERMISSION, IF, IN THE OPINION OF THE AUTHORITY, THE CONDITIONS OF THE PERMIT ARE NOT BEING COMPLIED WITH. THIS APPROVAL DOES NOT EXEMPT THE PROPERTY OWNER/APPLICANT/AGENT FROM THE PROVISIONS OF ANY OTHER FEDERAL, PROVINCIAL OR MUNICIPAL STATUTES, REGULATIONS OR BY-LAWS, OR ANY RIGHTS UNDER COMMON LAW.

TIMING OF WORKS

1. WORKS SHALL BE COMPLETED DURING THE DESIGNATED IN-WATER WORKS WINDOW SET OUT BY MNRF/DO.
2. TREE CLEARING IS TO BE COMPLETED OUTSIDE THE BIRD NESTING SEASON (APRIL 1ST TO AUGUST 1ST) TO COMPLY WITH THE FEDERAL MIGRATORY BIRDS CONVENTION ACT. ANY TREES THAT REQUIRE REMOVAL OUTSIDE OF THIS TIMING WINDOW MUST FIRST BE INSPECTED BY A QUALIFIED BIOLOGIST TO DETERMINE THE PRESENCE OF NESTING BIRDS.
3. THE WEATHER FORECAST SHOULD BE CONTINUALLY MONITORED TO ENSURE THAT WORKS ARE UNDERTAKEN ONLY DURING FAVOURABLE WEATHER CONDITIONS.
4. COMPLETE THE WORKS WITH MINIMAL AVOIDABLE INTERRUPTIONS ONCE THEY COMMENCE.

SITE AND MATERIAL MANAGEMENT

1. ALL CONSTRUCTION EQUIPMENT AND MATERIALS (IMPORTED OR EXCAVATED) MUST BE STORED AT LEAST 30 m AWAY FROM ANY WATERBODY IN A STABLE AREA ABOVE THE ACTIVE FLOODPLAIN, OR IN A DESIGNATED STAGING/STORAGE AREA.
2. IN THE EVENT OF AN UNEXPECTED STORM, ALL UNFIXED ITEMS THAT HAVE THE POTENTIAL TO CAUSE A SPILL OR AN OBSTRUCTION TO FLOW MUST BE MOVED A STABLE AREA ABOVE ACTIVE FLOODPLAIN.
3. STOCKPILES MUST BE LOCATED OUTSIDE THE ISOLATED WORK AREAS.
4. STABILIZE, TEMPORARILY OR PERMANENTLY, ANY DISTURBED AREAS AS WORK PROGRESSES, OR SOON AS CONDITIONS ALLOW.
5. MINIMIZE THE AREA OF DISTURBANCE TO THE EXTENT POSSIBLE. ALL DISTURBED GROUND LEFT INACTIVE FOR MORE THAN 30 DAYS SHALL BE STABILIZED USING APPROPRIATE EROSION CONTROL MEASURES AND AN APPROPRIATE SEED MIX AS NOTED WITHIN THE FINAL APPROVED RESTORATION PLAN.
6. ALL VEGETATION, ADJACENT TO THE WORK AREA, MUST BE PROTECTED AND DELINEATED WITH CONSTRUCTION FENCING OR TREE PROTECTION BARRIERS.
7. ALL GRADES IN THE AREA REGULATED BY THE CONSERVATION AUTHORITY MUST BE MAINTAINED OR MATCHED, UNLESS OTHERWISE AUTHORIZED IN THE APPLICABLE PERMIT.
8. AN AFTER-HOURS CONTACT NUMBER IS TO BE VISIBLY POSTED ONSITE FOR EMERGENCIES. ALL THE PLANS SHOULD HAVE NAME AND CONTACT INFO OF THE PERSON RESPONSIBLE FOR ESC MEASURES.

EROSION AND SEDIMENT CONTROL


1. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSTALLED PRIOR TO START OF WORKS. FOLLOWING INSTALLATION OF THE PROPOSED ESC MEASURES, A QUALIFIED AGENT OF THE PROPONENT (E.G. CAN-CSEC CERTIFIED MONITOR) WILL CONDUCT REGULAR SITE VISITS TO MONITOR ALL WORKS, PARTICULARLY THE CONDITION OF THE ESC MEASURES. DOWATERING, AND IN-OR NEAR-WATER WORKS, SHOULD CONCERNS ARISE, THE ENVIRONMENTAL MONITOR WILL CONTACT THE PROPONENT, THE CONSERVATION AUTHORITY, AND ANY OTHER APPROPRIATE PARTIES.
2. EROSION AND SEDIMENT CONTROLS MUST BE MAINTAINED DURING CONSTRUCTION, AND ANY REQUIRED REPAIRS OR REPLACEMENTS MUST BE COMPLETED WITHIN 24 HOURS AFTER THEY HAVE BEEN IDENTIFIED DURING THE MONITORING.
3. EROSION AND SEDIMENT CONTROLS MAY REQUIRE PERIODIC ADJUSTMENTS TO REFLECT CHANGING SITE CONDITIONS. THE CONTRACTOR WILL BE RESPONSIBLE FOR THESE ADJUSTMENTS TO ENSURE PROPER FUNCTION.
4. ANY CHANGES TO THE EROSION AND SEDIMENT CONTROL PLAN BEYOND MINOR ADJUSTMENTS MUST BE APPROVED BY THE CONTRACT ADMINISTRATOR.
5. ADDITIONAL EROSION AND SEDIMENT CONTROL SUPPLIES MUST BE KEPT ON SITE IN ORDER TO FACILITATE IMMEDIATE REPAIRS AND/OR UPGRADES AS NEEDED.
6. ALL TEMPORARY SEDIMENT CONTROLS MUST BE REMOVED AFTER THE CONTRACT ADMINISTRATOR DEEMS THE SITE TO BE STABLE.
7. THE PROJECT PROPONENT OR THEIR REPRESENTATIVE IS ULTIMATELY RESPONSIBLE FOR CONTROLLING SEDIMENT AND EROSION WITHIN THE CONSTRUCTION SITE FOR THE TOTAL PERIOD OF THE CONSTRUCTION.
8. IF EXCESSIVE SILTATION RESULTS FROM THE CONSTRUCTION ACTIVITIES, THE ONSITE SUPERVISOR/INSPECTOR AND/OR THE LOCAL REGULATORY BODY RESERVE THE RIGHT TO REQUEST ADDITIONAL ESC MEASURES WHICH WOULD BE INSTALLED PRIOR TO FURTHER CONSTRUCTION ACTIVITIES.

DELETERIOUS SUBSTANCE CONTROL/SPILL MANAGEMENT

1. PREVENT THE RELEASE OF SEDIMENT, SEDIMENT-LOADED WATER, RAW CONCRETE, CONCRETE LEACHATE OR ANY OTHER DELETERIOUS SUBSTANCES INTO ANY WATERBODY, RAVINE OR STORM SEWER SYSTEM.
2. ENSURE EQUIPMENT AND MACHINERY ARE IN GOOD OPERATING CONDITION (POWER WASHED), FREE OF LEAKS, EXCESS OIL AND GREASE.
3. NO EQUIPMENT REFUELLING OR SERVICING SHOULD BE UNDERTAKEN WITHIN 30 m OF ANY WATERCOURSE OR SURFACE WATER DRAINAGE.
4. A SPILL CONTAINMENT KIT MUST BE READILY ACCESSIBLE ON SITE IN THE EVENT OF A RELEASE OF A DELETERIOUS SUBSTANCE TO THE ENVIRONMENT. ONSITE STAFF MUST BE TRAINED IN ITS USE.
5. THE CONTRACT ADMINISTRATOR MUST BE NOTIFIED IMMEDIATELY IN THE EVENT OF A SPILL OF DELETERIOUS SUBSTANCE. ANY SEDIMENT SPILL FROM THE SITE SHOULD BE REPORTED TO MINISTRY OF ENVIRONMENT (SPILL ACTION CENTER) AT 1-800-268-6060.

WORK AREA ISOLATION

1. ALL WORK IN ISOLATED WORK AREAS MUST BE COMPLETED IN THE DRY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
2. CROSSING AN ACTIVE WATERCOURSE OR WETLAND BY EQUIPMENT, VEHICLES, PERSONNEL, ETC. IS NOT PERMITTED UNLESS APPROVED BY THE CONSERVATION AUTHORITY. ALL ACCESS TO WORK SITES SHALL BE FROM EITHER SIDES OF THE WATERCOURSE OR WETLAND.
3. THE UNWATERING DISCHARGE LOCATION MUST BE LOCATED AT LEAST 30 m FROM ANY WATERCOURSE OR WETLAND IN AN AREA WITH DENSE VEGETATIVE GROUND COVER, AND WHERE THE DISCHARGE CAN RETURN TO THE WATERBODY DOWNSTREAM OF THE WORK AREA OVER THE GROUND COVER.
4. FISH MUST BE REMOVED FROM THE WORK AREA ONCE ISOLATED. FISH SALVAGE MUST BE COMPLETED BY A QUALIFIED TECHNICIAN WITH A LICENSE FROM THE ONTARIO MINISTRY OF NATURAL RESOURCES AND FORESTRY.

1.	24/03/15	LD	FIRST CONCEPTUAL DESIGN SUBMISSION
	DATE	BY	REVISIONS
DESIGNED BY: LD		CHECKED BY: PV	
DRAWN BY: AS / SG		DATE: APRIL 2024	
<div>NOT FOR CONSTRUCTION SCALED FOR PLOT ON 'ARCH D'</div>		<div><p>M O R P H I X™ 36 Main St N., P.O. Box 205 Campbellville, Ontario L0P 1B0 T: 416.920.0926 www.geomorphix.com</p></div>	
24/03/15			
<div>BLOCK 1 BSS FRUITLAND-WINONA BLOCK 1 OWNERS GROUP, HAMILTON</div>			
<div>WATERCOURSE 5 CONCEPTUAL CHANNEL DESIGN DETAILS</div>			
PROJECT No.: 21043		DRAWING No.: DET-2	
SCALE: AS NOTED		SHEET 5 OF 5	